0-91-4	11-99						
FED. R	OAD DIST	T. NO.	ILLINOI	S FED.	AID	PROJECT	
STA.			TC	STA.			
90/94	199	9-161	-1	COO	K	75	11
RTE.	SEC	CTION		COUN.	TY	SHEETS	NO.



- COORDINATE DEMOLITION WITH THE PROPOSED CONSTRUCTION, MAINTENANCE OF THE FACILITY, AND APPROVED EQUIPMENT SHOP DRAWINGS. ALL OPENINGS ARE FOR ESTIMATE PURPOSE & SHALL BE COORDINATED WITH REVIEWED SHOP DRAWINGS.
- THE DEMOLITION OF THE STRUCTURAL SLAB AND BEAMS AT EL. -2'-9" SHALL BE SHORED PRIOR TO DEMOLITION. CONTRACTOR SHALL COORDINATE STRUCTURAL DEMOLITION WITH EQUIPMENT DEMOLITION TO MAINTAIN PUMP STATION IN
- DEMOLITION SHALL INCLUDE ALL ITEMS AND APPURTENANCES TO BE REMOVED AS REQUIRED TO COMPLETE THE WORK, WHETHER SPECIFICALLY IDENTIFIED OR NOT, SUCH THAT THE FACILITY IS COMPLETE AND OPERATIONAL.
- THE REMOVAL OF ELECTRICAL/MECHANICAL ITEMS INCLUDES THE REMOVAL OF ALL ASSOCIATED SUPPORTS, WIRING, BOXES AND CONDUIT.
- 5. USE CHIPPING MATERIAL AND ROCK SPLITTERS TO AVOID DAMAGING EXISTING REINFORCEMENT DURING CONCRETE DEMOLITION.
- CUT OR BEND EXISTING REINFORCEMENT TO CLEAR NEW OPENINGS, PIPE SLEEVES, WALL PIPES AND
- 7. LAP EXISTING REINFORCEMENT WITH NEW REINFORCEMENT.
- PATCH, REPAIR OR RESTORE ALL AREAS AFFECTED BY DEMOLITION AND EQUIPMENT REMOVAL TO MATCH ADJACENT SURFACES. PROVIDE UNIFORM APPEARANCE AND FILL UNNECESSARY OPENINGS.
- 9. MAIN PUMPS, MOTORS, COLUMNS AND SHAFTS SHALL BE SALVAGED AND DELIVERED TO A LOCATION WITHIN DISTRICT 1 AS PER ENGINEER.
- 10. FOR ADDITIONAL (E) SLABS/WALLS REMOVAL DUE TO NEW OPENING REQUIREMENT, (E) LADDERS/RAILINGS REPLACEMENT SEE DRAWINGS S-5, S-6, S-11 AND S-12.

## **NOTES:**

LEAD BASED PAINTS WERE USED ON THE PIPES. DEMOLITION CONTRACTOR SHALL HAVE THE LEAD PAINT ABATED AND PROPERLY DISPOSED PER THE REQUIREMENTS OF DIVISION 9, SECTION 9B OF THE SPECIFICATIONS AND REQUIREMENTS OF ALL RULES GOVERNING REMOVAL OF LEAD BASED PAINTS FROM THE U.S. ENVIRONMENTAL PROTECTION AGENCY (USEPA) CONTAINED IN THE FEDERAL REGISTER 10 CFR PART 745.

## **LEGEND**



REMOVAL WORK



- Removable Section With Lock

- NOTE 1

PLAN M-M

PLAN N-N\_\_\_\_\_EL -2'-9"

(TYP. ALL PIPES)

AND DUCTWORK

23'-6

- NOTE 1

(TYP. ALL PIPES)

Removable Section With Lock

REMOVE FAN AND DUCTWORK

REMOVE PUMPS. SUPPORT FRAME &

INSTALL FLOOR PLATE SEE DWG. S-6

SLEEVES TO REMAIN IN WALL

5'-6" 5'-6"

REMOVE EXISTING PUMP COLUMN, 20" DISCHARGE PIPING, COUPLING AND

FLAP VALVE (TYP. 7 PUMPS)

, (4)

REMOVE EXISTING LOUVER ABOVE DOOR

REMOVE HEATER-

REMOVE GAS METER AND PIPING

TO BELOW GRADE.

MAIN AND CAP THE

REMOVE INSULATING GLASS AND PROVIDE OPENING FOR

LOUVER AND DAMPER D-3-

AND COVER SEE DWG. A-1

ILLINOIS DEPARTMENT OF TRANSPORTATION

**MECHANICAL DEMOLITION - SHEET 1** 

SCALE: VERT. NO SCALE HORIZ. NO SCALE DATE: 3/23/2010

CHECKED BY: A.M.