

90% FED.  
10% STATE  
URBAN

ROADWAY

RETAINING WALLS

BOX CULVERTS

SIGNING

ELECTRICAL

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				J000-2A	Y007	Y007	Y002-1C	Y030-1E
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	102	102				
63500105	DELINEATORS	EACH	19	19				
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	100	100				
63700900	CONCRETE BARRIER BASE	FOOT	100	100				
66400305	CHAIN LINK FENCE, 6'	FOOT	1,076	1,076				
• 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	4,650	4,650				
• 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1				
• 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5				
67100100	MOBILIZATION	L SUM	1	1				
• 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
• 70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,349	14,349				
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	199	199				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	235				235	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	52				52	
* 72000300	SIGN PANEL - TYPE 3	SQ FT	157				157	
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	83				83	
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2,508				2,508	
* 72900200	METAL POST - TYPE 3	FOOT	610				610	
* 73400100	CONCRETE FOUNDATIONS	CU YD	5				5	
* 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	11				11	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34,019	34,019				
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	25	25				
• 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	138	138				
• 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	23,026	23,026				
• 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	301	301				
• 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	52	52				
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	505	505				
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	26	26				
• 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,770	1,770				
• 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1
80400200	UTILITY ELECTRIC SERVICE CONNECTION	L SUM	1					1
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	106					106

• SPECIALTY ITEM

McDonough Associates Inc.  
Engineers, Architects  
130 East Randolph Street, Chicago, Illinois 60601

FILE NAME	USER NAME	DESIGNED	REVISED
ENGINEER		MJT	
		MCJ	
PLOT SCALE	CHECKED	DU	REVISED
PLOT DATE	DATE	12/18/09	REVISED

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF SHEETS STA. TO STA.

F.A.I.	SECTION	TOTAL SHEETS	SHEET NO.
99	(99-182)AC-3	524	9
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		CONTRACT NO. 60C31	

FINAL