

ROADWAY
90% FED.
10% STATE
URBAN

RETAINING WALLS

BOX CULVERTS

SIGNING

ELECTRICAL

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				J000-2A	Y007	Y007	Y002-1C	Y030-1E
81700365	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 1/0	FOOT	143					143
81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	2,636					2,636
82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	10					10
83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	1					1
X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2				
X0322208	TEMPORARY STORM SEWER PLUGS	EACH	7	7				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	95	95				
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	72	72				
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	9					9
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	12,145	12,145				
X0324044	EROSION CONTROL TEMPORARY PIPE SLOPE DRAIN	EACH	13	13				
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	5	5				
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,420	1,420				
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	2,840	2,840				
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	66,532	66,532				
X0325841	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	36	36				
X0326020	UTILITY PROTECTION PAD	SQ YD	1,290	1,290				
X0712400	TEMPORARY PAVEMENT	SQ YD	1,792	1,792				
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	1,233	1,233				
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	32,893	32,893				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	8	8				
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	1,925	1,925				
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12				
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	12	12				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	66,788	66,788				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0022800	FENCE REMOVAL	FOOT	19,395	19,395				
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1				
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3	3				
Z0076600	TRAINEES	HOUR	1,000	1,000				
K1004469	PERENNIAL PLANTS, PRAIRIE TYPE	UNIT	1.60	1.60				
K1004485	PERENNIAL PLANTS, WETLAND TYPE	UNIT	11.84	11.84				
66411905	TEMPORARY FENCE (SPECIAL)	FOOT	21,171	21,171				
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	18,002	18,002				

• SPECIALTY ITEM
⊙ Y080

FILE NAME = D160C31-SHT-S0006.dgn	USER NAME = TKluegel	DESIGNED - MJT	REVISED -
PLOT SCALE = 1/8"=1'	CHECKED - DLT	DRAWN - MJT	REVISED -
PLOT DATE = 12/16/2009	DATE - 12/18/09		REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 6 OF 7 SHEETS STA. TO STA.

F.A.I RTE. 55	SECTION (99-1&2)AC-3	COUNTY WILL	TOTAL SHEETS 524	SHEET NO. 10
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60C31	

Rev.

FINAL