

EROSION CONTROL SCHEDULE I-55

	25100115	28000250	28000300	28000500	28000510	X6640200	X0323426	28000400	X0323974	X0324045	X0324774	X0324775	28100107	28200200
	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	INLET AND PIPE PROTECTION	INLET FILTERS	TEMPORARY CHAIN LINK FENCE	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	PERIMETER EROSION BARRIER	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	STONE RIPRAP, CLASS A4	FILTER FABRIC
	ACRE	POUND	EACH	EACH	EACH	FOOT	EACH	FOOT	FOOT	EACH	SQ YD	SQ YD	SQ YD	SQ YD
SHEET														
EC-1	1.34	269	6	1	-	52	-	1,389	417	-	-	-	40	30
EC-2	3.91	782	20	4	-	597	-	3,246	974	2	566	1,132	-	-
EC-3	13.87	2,773	17	4	3	152	15	5,438	1,631	-	94	189	-	-
EC-4	15.68	3,137	18	5	-	-	-	6,953	2,086	-	-	-	-	-
EC-5	9.92	1,985	9	1	1	159	5	6,164	1,849	1	316	633	-	-
EC-6	16.73	3,347	18	2	-	67	-	4,323	1,297	-	-	-	-	-
EC-7	6.92	1,383	2	-	-	-	-	955	287	-	-	-	-	-
EC-8	4.22	843	15	4	6	722	30	3,370	1,011	-	-	-	-	-
EC-9	2.61	522	8	4	3	-	15	1,685	506	-	-	-	-	-
EC-10	1.98	396	19	2	-	-	-	1,347	404	-	-	-	-	-
EC-11	1.37	274	6	1	-	-	-	885	266	-	-	-	-	-
EC-12	1.15	230	-	-	-	-	-	1,034	310	1	312	623	20	15
EC-13	-	-	-	-	-	-	-	-	-	-	-	-	-	-
EC-14	-	-	-	-	-	-	-	-	-	-	-	-	-	-
EC-15	1.78	356	-	-	-	-	-	-	-	-	-	-	-	-
SUB-TOTAL	81.50	16,300	138	28	13	1,750	65	36,790	11,040	4	1,290	2,580	60	45
AT THE ENGINEER'S DISCRETION	8.20	1,630	14	3	2	175	7	3,680	1,105	1	130	260	6	5
GRAND TOTAL	89.70	17,930	152	31	15	1,925	72	40,470	12,145	5	1,420	2,840	66	50

	28000200	X0324044
	EARTH EXCAVATION FOR EROSION CONTROL	EROSION CONTROL TEMPORARY PIPE SLOPE DRAIN
	CU YD	EACH
SHEET		
EC-1	140	-
EC-2	-	-
EC-3	-	2
EC-4	-	6
EC-5	-	1
EC-6	-	2
EC-7	-	-
EC-8	-	-
EC-9	-	-
EC-10	-	-
EC-11	-	-
EC-12	70	-
EC-13	-	-
EC-14	-	-
EC-15	-	-
SUB-TOTAL	210	11
AT THE ENGINEER'S DISCRETION	21	2
GRAND TOTAL	231	13

McDonough Associates Inc.
 Engineers / Architects
 130 East Randolph Street, Chicago, Illinois 60601

FILE NAME =	USER NAME = #USER#	DESIGNED - TRK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F./S. \$	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - TRK	REVISED -			\$RTE\$	\$SECT\$	\$CNTY\$	534	25
	PLOT SCALE = #SCALE#	CHECKED - DLT	REVISED -					CONTRACT NO. #CON#		
	PLOT DATE = #DATE#	DATE - #SUBDATE#	REVISED -			SCALE: NONE	SHEET NO. 8 OF 11 SHEETS	STA. TO STA.	FED. ROAD DIST. #DIST# ILLINOIS FED. AID PROJECT	

\$\$\$SUBTYPES\$