

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	55	55					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	87	87					70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5					
25200110	SODDING, SALT TOLERANT	SO YD	87	87					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16461	16461					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	61	61					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	657	657					
40600300	AGGREGATE (PRIME COAT)	TON	301	301					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45562	45562					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	113	113					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1844	1844					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3097	3097					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	77	77					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	172	172					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	803	803					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5487	5487					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6305	6305					78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	657	657					
42001200	PAVEMENT FABRIC	SO YD	130	130					78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45545	45545					
42001300	PROTECTIVE COAT	SO YD	1133	1133					78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1844	1844					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	75059	75059					78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	77	77					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	520	520					78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	172	172					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	6562	6562					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	470	470					
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	158	158					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	365	365					
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	130	130					88600600	DETECTOR LOOP REPLACEMENT	FOOT	1143	1143					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	25	25					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	206.6	206.6					
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	1513	1513					Z0017202	DOWEL BARS 1 1/2"	EACH	860	860					
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SO YD	631	631					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	45	45					
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SO YD	379	379					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
44213200	SAW CUTS	FOOT	408	408														
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	110	110														
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17														
60404950	FRAMES AND GRATES, TYPE 24	EACH	12	12														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	6562	6562														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1														
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1														