

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SN016-1251 X271-2A	SN016-1252 X271-2A
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	122	122					
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	2000	2000					
X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	3	3					
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	3	3					
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	318				318		
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	1	1					
X0323651	REMOVE AND REINSTALL EXISTING LIGHTING UNIT	EACH	12		12				
* X0323670	PREFORMED DETECTOR LOOP	FOOT	387				387		
X0323830	DRAINAGE SCUPPERS, DS11	EACH	24					18	6
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	11082					4262	6820
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	26		26				
* X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	11		11				
X0324752	STORM SEWER TO BE FILLED	CU YD	115	115					
* X0324866	REMOVE AND REINSTALL SURVEILLANCE CABINET	EACH	1				1		
X0712400	TEMPORARY PAVEMENT	SQ YD	2995	2995					
X0326301	EXPANDED POLYSTYRENE FILL	CU YD	705	705					
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	169,246	169,246					
X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	534	534					
X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	4109	4109					
X0326107	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	FOOT	15671	15671					
* X0326133	TEMPORARY WOOD POLE, 45 FEET, CLASS 5	EACH	44				44		
X0326382	CONCRETE BARRIER BASE (SPECIAL)	FOOT	8133	8133					
* XX007994	FIBER OPTIC SPLICE	EACH	28				28		
X0326520	TEMPORARY THRIE BEAM STEEL PLATE GUARD RAIL, TYPE D REMOVAL (SPECIAL)	FOOT	60	60					
X0326527	TEMPORARY THRIE BEAM STEEL PLATE GUARD RAIL, TYPE D (SPECIAL)	FOOT	60	60					
X0326593	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 1/2" DIAMETER, 6 FOOT LENGTH	EACH	14	14					
* X0326836	REMOVE AND REINSTALL VIDEO CAMERA AND EQUIPMENT	EACH	2				2		
X4400198	CONCRETE BARRIER REMOVAL (SPECIAL)	FOOT	772	772					
X6020088	MANHOLES, TYPE A, 8"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
X6370150	CONCRETE BARRIER, VARIABLE CROSS-SECTION, 32" HEIGHT	FOOT	8073	8073					
X6640210	TEMPORARY CHAIN LINK FENCE (PORTABLE)	FOOT	1260	1260					
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	23	23					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	399	399					

* Specialty Items

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - CAC	REVISED -			57	1414.2B	COOK	516	11
	PLOT DATE =	CHECKED - JDF	REVISED -			CONTRACT NO. 60J27				
DATE - 3/18/2010				SCALE: NTS		SHEET NO. 8 OF 9 SHEETS		STA. TO STA.		
						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				