

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE															
CODE NO	ITEM	UNIT	IC00-2A									CODE NO	ITEM	UNIT	IC00-2A																					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	44	44								70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	385	385																				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1156	1156								* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	353	353																				
25200110	SODDING, SALT TOLERANT	SQ YD	1156	1156								* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43187	43187																				
40600200 40600300	BITUMINOUS MATERIALS (PRIME COAT) AGGREGATE (PRIME COAT)	TON	35	35								* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1684	1684																				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	68	68								* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	440	440																				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3460	3460								* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	385	385																				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1								* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	570	570																				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	222	222								78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	570	570																				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	250	250								* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1735	1735																				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3794	3794								X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103																				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3983	3983								X4421000	PARTIAL DEPTH PATCHING	TON	202	202																				
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	45181	45181								X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1200	1200																				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1300	1300								WP 70018500	DRAINAGE STRUCTURE TO BE CLEANED	EACH	3	3																				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1486	1486								48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	407	407																				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	382	382								67100100	MOBILIZATION	L SUM	1	1																				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	16	16																																
44201759 44300200	CLASS D PATCHES, TYPE IV, 9 INCH STRIP REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	845	845																																
60300105	FRAMES AND GRATES TO BE ADJUSTED	FOOT	9833	9833																																
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7																																
60300405 67000400	VALVE BOX FRAMES TO BE ADJUSTED ENGINEER'S FIELD OFFICE, TYPE A	EACH	6	6																																
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	CAL MO L SUM	3 1	3 1																																
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1																																
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																																
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																																
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1973	1973																																
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	353	353																																
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43187	43187																																
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1684	1684																																
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	440	440																																

FILE NAME =	USER NAME = jaysa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. ROUTE 31 (WILDROSE SPRINGS DR. TO HORNE ST.) SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pawork\jaysa\0103516\014410-str-plan.dgn		DRAWN -	REVISED -			3887	2010-002RS	KANE	85	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			SCALE: N/A		SHEET NO. OF SHEETS		STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
PLOT DATE = 3/17/2010		DATE -	REVISED -								

Rev. 5-26-10