

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000						CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	107	107						*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	135	135					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	32	32						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52					
25200110	SODDING, SALT TOLERANT	SO YD	32	32						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10															
40600300	AGGREGATE (PRIME COAT)	TON	51	51															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	19	19															
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	500	500															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	46	46															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1065	1065															
42001300	PROTECTIVE COAT	SO YD	63	63															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	12350	12350															
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	185	185															
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SO YD	278	278															
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SO YD	247	247															
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SO YD	93	93															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	212	212															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	34500	34500															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	37	37															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5780	5780															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	105	105															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	11500	11500															
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	37	37															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5780	5780															
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	105	105															

\* SPECIALTY ITEMS