

SOIL EROSION AND SEDIMENT CONTROL NOTES

1. SEDIMENTATION AND EROSION CONTROL STANDARDS

THE FOLLOWING STANDARDS MUST BE SATISFIED:

- A. ALL AREAS LOCATED DOWNSTREAM FROM DISTURBED AREAS OF A DEVELOPMENT SITE SHALL BE PROTECTED FROM POTENTIAL INCREASE OF EROSION AND SEDIMENTATION RESULTING FROM UPSTREAM ACTIVITIES.
- B. SOIL EROSION AND SEDIMENT CONTROL FEATURES SHALL BE CONSTRUCTED AND FUNCTIONAL PRIOR TO OR CONCURRENTLY WITH THE START OF DISTURBANCE.
- C. PERMANENT STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICAL IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED; BUT IN NO CASE SHALL THESE MEASURES BE INSTALLED MORE THAN 14 DAYS AFTER THE CONSTRUCTION IN THE AREA TEMPORARILY OR PERMANENTLY CEASES.

2. SEDIMENTATION AND EROSION CONTROL METHODS

THE FOLLOWING SEDIMENTATION AND EROSION CONTROL METHODS MUST BE INSTALLED AND MAINTAINED:

- A. ALL STORM SEWER STRUCTURES THAT RECEIVE RUNOFF DURING CONSTRUCTION SHALL INCLUDE INLET PROTECTION TO PREVENT DEBRIS AND EXCESSIVE SEDIMENT FROM ENTERING THE STORM SEWER PIPING SYSTEM. THESE PROTECTIVE MEASURES SHALL BE PROPERLY INSTALLED, MAINTAINED, AND REMOVED IN THEIR ENTIRETY AFTER THE AREA TRIBUTARY TO THE STORM STRUCTURE IS STABILIZED.
- B. DISCHARGES FROM DEWATERING OPERATIONS SHALL ENTER OR BE ROUTED TO A SEDIMENT AND EROSION CONTROL SYSTEM OR DEVICE.
- C. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE PROPERLY STABILIZED OR DISPOSED.
- D. A STABILIZED CONSTRUCTION ENTRANCE SHALL BE LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING THE CONSTRUCTION SITE. THE STABILIZED CONSTRUCTION ENTRANCE SHALL BE PERIODICALLY MAINTAINED TO REMOVE MUD AND DEBRIS. THE STABILIZED CONSTRUCTION ENTRANCE SHALL CONSIST OF AN APPROPRIATE GEOTEXTILE FABRIC COVERED WITH AT LEAST SIX INCHES OF CLEAN STONE THAT IS AT LEAST TWO (2) INCHES IN DIAMETER.
- E. TEMPORARY EARTHEN EMBANKMENTS, GRADE TRANSITIONS AND BERMS SHALL BE CONSTRUCTED WITH SIDE SLOPES NO STEEPER THAN 3H:1V. SIDE SLOPES BELOW NORMAL WATER LEVEL SHALL BE NO STEEPER THAN 2H:1V. MORE GRADUAL SLOPES MAY BE REQUIRED FOR SOILS THAT EASILY ERODE.

3. MAINTENANCE

ALL TEMPORARY MEASURES AND PERMANENT EROSION AND SEDIMENT CONTROL MUST BE MAINTAINED IN AN EFFECTIVE WORKING CONDITION AS IDENTIFIED BY REQUIRED INSPECTIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE FOLLOWING:

- A. REPAIR, REPLACE OR MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES AFTER A SINGULAR OR CUMULATIVE RAINFALL EVENT(S) OF 0.5 INCH OR MORE OVER A TWENTY-FOUR-HOUR PERIOD.
- B. MAKE ADJUSTMENTS TO THE SEDIMENTATION AND EROSION CONTROL PLAN AND METHODS, AS NEEDED, TO ACCOMPLISH THE INTENDED PURPOSE.
- C. ALL ADJACENT ROADWAYS MUST BE KEPT CLEAR OF DEBRIS, INSPECTED DAILY, AND CLEANED WHEN NECESSARY OR AS DETERMINED BY THE VILLAGE OF CARY OR THE ENGINEER.

4. INSPECTIONS

- A. THESE PLANS FOR UPGRADING, STRIPPING, EXCAVATING, AND FILLING WORK, BEAR THE STAMP OF APPROVAL OF THE ENFORCEMENT OFFICER. THESE PLANS SHALL BE MAINTAINED AT THE SITE DURING THE PROGRESS OF THE WORK. THE DISTRICT AND/OR ENGINEER SHALL MAKE INSPECTIONS AND MAINTAIN ON-SITE RECORDS OF SUCH INSPECTIONS AT THE INTERVALS SPECIFIED BELOW:
 - I. UPON COMPLETION OF INSTALLATION OF SEDIMENT AND RUNOFF CONTROL MEASURES (INCLUDING PERIMETER CONTROLS AND DIVERSIONS), PRIOR TO PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING;
 - II. AFTER ROUGH GRADING;
 - III. AFTER FINAL GRADING; AND
 - IV. WEEKLY AND AFTER EACH RAINFALL EVENT OF 0.5 INCH OR MORE OVER A TWENTY-FOUR-HOUR PERIOD.
- B. ANY NECESSARY REPAIRS TO SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MADE AND REPORTED IN THE ON-SITE INSPECTION RECORDS. COPIES OF THE INSPECTION RECORDS SHALL BE SUBMITTED TO THE ENFORCEMENT OFFICER IN A MONTHLY INSPECTION REPORT.

5. NOTIFICATIONS

- TO FACILITATE ENFORCEMENT OFFICER COMPLIANCE INSPECTIONS THE DISTRICT AND/OR ENGINEER SHALL NOTIFY THE ENFORCEMENT OFFICER WITHIN TWO (2) WORKING DAYS OF THE COMPLETION OF THE CONSTRUCTION STAGES SPECIFIED BELOW:
- A. UPON COMPLETION OF INSTALLATION OF SEDIMENT AND RUNOFF CONTROL (CONTROLS AND DIVERSIONS), PRIOR TO PROCEEDING WITH ANY OTHER EARTH DISTURBANCE OR GRADING;
 - B. AFTER ROUGH GRADING;
 - C. AFTER FINAL STABILIZATION AND LANDSCAPING, PRIOR TO REMOVAL OF SEDIMENT CONTROLS.
- IF STRIPPING, CLEARING, GRADING AND/OR LANDSCAPING ARE TO BE DONE IN PHASES OR AREAS, THE DISTRICT AND/OR ENGINEER SHALL GIVE NOTICE AT THE COMPLETION OF EACH OF THE ABOVE WORK STAGES IN EACH PHASE OR AREA.

6. SPECIAL PRECAUTIONS

- A. IF AT ANY STAGE OF THE GRADING ON THE SITE, THE ENFORCEMENT OFFICER DETERMINES BY INSPECTION THAT THE NATURE OF THE SITE IS SUCH THAT FURTHER WORK AUTHORIZED BY AN EXISTING PERMIT IS LIKELY TO IMPERIL ANY PROPERTY, PUBLIC WAY, STREAM, LAKE, WETLAND, OR DRAINAGE STRUCTURE, THE ENFORCEMENT OFFICER MAY REQUIRE, AS A CONDITION OF ALLOWING THE WORK TO BE DONE, THAT SUCH REASONABLE SPECIAL PRECAUTIONS BE TAKEN AS ARE CONSIDERED ADVISABLE TO AVOID THE LIKELIHOOD OF SUCH PERIL. "SPECIAL PRECAUTIONS" MAY INCLUDE, BUT SHALL NOT BE LIMITED TO, A MORE LEVEL EXPOSED SLOPE, CONSTRUCTION OF ADDITIONAL DRAINAGE FACILITIES, BERMS, TERRACING, COMPACTION, OR CRIBBING, INSTALLATION OF PLANT MATERIALS FOR EROSION CONTROL, AND RECOMMENDATIONS OF A REGISTERED SOILS ENGINEER AND/OR ENGINEERING GEOLOGIST WHICH MAY OUTLINE REQUIREMENTS FOR FURTHER WORK.
- B. WHERE IT APPEARS THAT STORM DAMAGE MAY OCCUR DUE TO INCOMPLETE GRADING AT SITE, WORK MAY BE STOPPED AND THE CONTRACTOR REQUIRED TO INSTALL TEMPORARY STRUCTURES OR TAKE SUCH OTHER MEASURES AS MAY BE REQUIRED TO PROTECT ADJOINING PROPERTY OR THE PUBLIC SAFETY. WHERE UNUSUAL SITE CONDITIONS PREVAIL, THE ENFORCEMENT OFFICER MAY SPECIFY THE START AND END DATES FOR GRADING OPERATIONS OR MAY REQUIRE THAT THE OPERATIONS BE CONDUCTED IN SPECIFIC STAGES SO AS TO ENSURE COMPLETION OF PROTECTIVE MEASURES OR DEVICES PRIOR TO THE ADVENT OF SEASONAL RAINS.

7. MCHENRY COUNTY SOIL EROSION AND SEDIMENT CONTROL

- A. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. AREAS OF THE DEVELOPMENT SITE THAT ARE NOT TO BE GRADED SHALL BE PROTECTED FROM CONSTRUCTION TRAFFIC OR OTHER DISTURBANCE UNTIL FINAL SEEDING IS PERFORMED.
- B. SOIL AND MATERIAL STOCKPILES SHALL NOT BE LOCATED IN A FLOOD-PRONE AREA OR A DESIGNATED BUFFER PROTECTING WATERS OF THE UNITED STATES OR ISOLATED WATERS OF MCHENRY COUNTY.
- C. THE CONTRACTOR SHALL PROVIDE ADEQUATE RECEPTACLES FOR THE DISPOSITION OF ALL CONSTRUCTION MATERIAL DEBRIS GENERATED DURING THE DEVELOPMENT PROCESS. THE CONTRACTOR SHALL NOT CAUSE OR PERMIT THE DUMPING, DEPOSITING, DROPPING, THROWING, DISCARDING OR LEAVING OF CONSTRUCTION MATERIAL DEBRIS UPON OR INTO ANY DEVELOPMENT SITE, CHANNEL, EATERS OF THE U.S. OR ISOLATED WATERS OF MCHENRY COUNTY. THE CONTRACTOR SHALL MAINTAIN THE DEVELOPMENT SITE FREE OF CONSTRUCTION MATERIAL DEBRIS.

• F.A.U. 4051 THREE OAKS ROAD
• F.A.U. 4052 SILVER LAKE ROAD

COPYRIGHT © 2010 BY BAXTER & WOODMAN, INC. ... V:\projects\060197-P2-ER-NOTES.sht
DESIGNED BY MWP/DSH
DRAWN BY MAC
CHECKED BY RWL
DATE 03-01-10
REVISED - 01-04-10 PER IDOT
REVISED -
REVISED -
FILE -060197-P2-ER_NOTES.sht



DESIGNED -	MWP/DSH	REVISED -	01-04-10 PER IDOT
DRAWN -	MAC	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	03-01-10	FILE -	-060197-P2-ER_NOTES.sht

**VILLAGE OF CARY, ILLINOIS
THREE OAKS ROAD AND SILVER LAKE ROAD
ARRA INTERSECTION IMPROVEMENTS**

EROSION AND SEDIMENT CONTROL NOTES

SCALE: NONE

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	09-00058-00-CH	MCHENRY	53	17
C-91-511-10			CONTRACT NO. 63381	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT: ARA-900316351				