

26 THERMOPLASTIC PAVEMENT MARKING - LINE 5"					
5" SOLID WHITE LINE (FEET)					
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	DESCRIPTION	QUANTITY (FEET)
OLD MCHENRY ROAD		LT	41.4	RETURN AT INTERSECTION	41.4
OLD MCHENRY ROAD		RT	79.2	RETURN AT INTERSECTION	79.2
KRUGER ROAD		LT	42.9	RETURN AT INTERSECTION	42.9
KRUGER ROAD		LT	45.5	RETURN AT INTERSECTION	45.5
KRUGER ROAD		RT	50.5	RETURN AT INTERSECTION	50.5
KRUGER ROAD		RT	49.8	RETURN AT INTERSECTION	49.8
39+55	41+70.61	RT	219.2*	EDGE LINE	219.2
HOLMES AVENUE		RT	35.7	RETURN AT INTERSECTION	35.7
HOLMES AVENUE		RT	46.6	RETURN AT INTERSECTION	46.6
LOCHANORA DRIVE		LT	56.8	RETURN AT INTERSECTION	56.8
LOCHANORA DRIVE		LT	41.3	RETURN AT INTERSECTION	41.3
MILTON ROAD		RT	42.6	RETURN AT INTERSECTION	42.6
MILTON ROAD		RT	35.0	RETURN AT INTERSECTION	35.0
MILTON ROAD		LT	57.1	RETURN AT INTERSECTION	57.1
MILTON ROAD		LT	48.8	RETURN AT INTERSECTION	48.8
TOPANGA TRAIL		LT	19.2	RETURN AT INTERSECTION	19.2
TOPANGA TRAIL		LT	19.1	RETURN AT INTERSECTION	19.1
POND SHORE DRIVE		LT	39.1	N AT INTERSECTION	39.1
POND SHORE DRIVE		LT	40.1	RETURN AT INTERSECTION	40.1
SCHWERMAN ROAD		LT	37.1	RETURN AT INTERSECTION	37.1
SCHWERMAN ROAD		LT	58.8	N AT INTERSECTION	58.8
SCHWERMAN ROAD		RT	39.3	RETURN AT INTERSECTION	39.3
SCHWERMAN ROAD		RT	80.3	RETURN AT INTERSECTION	803.0
BARNSWALLOW LANE		LT	62.5	RETURN AT INTERSECTION	62.5
BARNSWALLOW LANE		LT	62.5	RETURN AT INTERSECTION	62.5
IL RT 176		LT	73.3	RETURN AT INTERSECTION	73.3
IL RT 176		RT	71.5	RETURN AT INTERSECTION	71.5
PAY ITEM					
78000300					TOTAL 2217.8

27 THERMOPLASTIC PAVEMENT MARKING - LINE 6"					
6" SOLID WHITE LINE					
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	DESCRIPTION	QUANTITY (FEET)
1+62.59	3+22.59	LT	160.0	TURN LANE SOLID	160.0
1+62.59	5+22.59	LT	360.0	TURN LANE SOLID	360.0
3+22.59	5+22.59	LT	200.0	2-6' SKIP DASH	50.0
5+22.59	7+22.59	LT	200.0	2-6' SKIP DASH	50.0
39+55	40+60.8	RT	105.8	2-6' SKIP DASH	26.5
40+60.8	41+65.8	RT	105.0	TURN LANE SOLID	105.0
184+25	185+30	RT	105.0	2-6' SKIP DASH	26.3
185+30	187+10	RT	180.0	TURN LANE SOLID	180.0
PAY ITEM					
78000400					TOTAL 957.7

*SEE STA. EQUATION ON PLANS

28 THERMOPLASTIC PAVEMENT MARKING - LINE 12"					
12" SOLID YELLOW LINE					
FROM	TO	NUMBER OF STRIPES	AVG. LENGTH	DESCRIPTION	QUANTITY (FEET)
5+22.59	11+22.59	22	11.4	MEDIAN DIAGONAL	249.8
184+25	185+30	3	3.3	MEDIAN DIAGONAL	9.9
PAY ITEM					
78000600					TOTAL 259.8

29 THERMOPLASTIC PAVEMENT MARKING - LINE 24"					
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	DESCRIPTION	QUANTITY (FEET)
1+62.59		LT	43.93	STOP BAR	43.93
187+10		RT	27.49	STOP BAR	27.49
PAY ITEM					
78000650					TOTAL 71.4

30 PAINT PAVEMENT MARKING - LINE 4"					
4" 10/30 SKIP/DASH YELLOW LINE = LENGTH X 0.25					
4" SOLID YELLOW WITH 10/30 SKIP/DASH = LENGTH X 1.275					
4" DOUBLE SOLID YELLOW LINE = LENGTH X 2					
4" 10/30 SKIP/DASH WHITE LINE = LENGTH X 0.25					
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	DESCRIPTION	QUANTITY (FEET)
11+22.59	22+54.74	C/L	1132.2	D. YELLOW C/L	2264.3
22+96.5	41+65	C/L	1858.1	D. YELLOW C/L	3716.2
42+19.03	50+10	C/L	780.17*	D. YELLOW C/L	1560.3
65+05	66+76.12	C/L	171.1	D. YELLOW C/L	342.2
67+25.35	67+88	C/L	62.7	D. YELLOW C/L	125.3
84+25	111+30.53	C/L	2716.05*	D. YELLOW C/L	5432.1
111+89.00	113+47.07	C/L	158.1	D. YELLOW C/L	316.1
114+10.5	130+67.57	C/L	1634.1*	D. YELLOW C/L	3268.2
131+08.89	134+74.03	C/L	365.1	D. YELLOW C/L	730.3
135+25.97	148+80.68	C/L	1354.7	D. YELLOW C/L	2709.4
149+70.00	150+21.50	C/L	51.5	D. YELLOW C/L	103.0
150+21.5	152+72	C/L	250.5	10-30' SOLID SKIP	313.1
152+82.90	160+24.78	C/L	741.9	10-30' SOLID DASH	185.5
160+24.78	161+80.43	C/L	155.7	10-30' SOLID SKIP	194.6
161+80.43	162+50	C/L	69.6	D. YELLOW C/L	139.1
162+83.70	165+80	C/L	296.3	D. YELLOW C/L	592.6
PAY ITEM					
78001110					TOTAL 21992.4

*SEE STA. EQUATION ON PLANS

31 PAINT PAVEMENT MARKING - LINE 5"					
5" SOLID WHITE LINE (FEET)					
FROM	TO	LEFT OR RIGHT	LENGTH (FEET)	DESCRIPTION	QUANTITY (FEET)
1+83.76	22+28.3	LT	2044.5	EDGE LINE	2044.5
1+94.95	22+26.06	RT	2031.1	EDGE LINE	2031.1
23+21.16	50+10	LT	2678.04*	EDGE LINE	2678.0
23+16.81	39+55	RT	1627.39*	EDGE LINE	1627.4
42+32.70	50+10	RT	777.3	EDGE LINE	777.3
65+05	66+38.1	LT	133.1	EDGE LINE	133.1
65+05	67+80	RT	275.0	EDGE LINE	275.0
67+44.8	67+80	LT	43.2	EDGE LINE	35.2
84+25	113+30.06	LT	2915.65*	EDGE LINE	2915.7
84+25	111+15.90	RT	2700.55*	EDGE LINE	2700.6
111+94	148+99	RT	3682*	EDGE LINE	3682.0
114+42.37	130+67.57	LT	1602.2*	EDGE LINE	1602.2
131+08.89	134+58.84	LT	350.0	EDGE LINE	350.0
135+31.85	148+70.62	LT	1338.8	EDGE LINE	1338.8
149+54.96	162+31.13	LT	1307.1*	EDGE LINE	1307.1
150+07.94	165+80	RT	1583.0*	EDGE LINE	1583.0
163+03.25	165+80	LT	276.8	EDGE LINE	276.8
184+25	187+25.51	LT	300.5	EDGE LINE	300.5
184+25	186+94.54	RT	269.5	EDGE LINE	269.5
PAY ITEM					
78001120					TOTAL 25927.6


*SEE STA. EQUATION ON PLANS

32 RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL &				
From	To	Removal	Proposed	
1+62.83	14+47.07	71	71	
26+95.87	41+46.73	30	65	
88+01.29	105+50.94	46	0	
131+08.87	142+05.56	28	0	
TOTAL		175	136	
PAY ITEM		78300200	78100100	

33 HEAVY-DUTY HANDHOLES TO BE ADJUSTED (SPECIAL)			
STATION	OFFSET	LT/RT	DESCRIPTION
1+58.83	13.5	LT	TRAFFIC - HDHH
TOTAL			1
PAY ITEM			
81400215			

34 DETECTOR LOOP REPLACEMENT			
From	To	Quantity (LF)	
1+47.83	1+83.83	192	
186+84	187+65.00	192	
PAY ITEM			
88600600			TOTAL 384.0

REVISIONS / REMARKS				
NO.	DESCRIPTION	DATE	BY	SURVEYOR
1	PER LCDOT REVIEW COMMENTS	10/06/09	EB	DSCNR/LIAISON
				PLOTTED BY: FUSRNF REDAT/EEB



FAIRFIELD ROAD
RESURFACING 2009



FAIRFIELD RD RESURFACING
SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH 49	113	08-00999-01-RS	10	60