


LC4110	
APPROVED BY: M. G. ZEMAITIS DATE: APRIL 1, 2007	LAKE COUNTY Division of Transportation
TYPICAL MINOR ACCESS TREATMENT ON RESURFACING PROJECTS	
REVISIONS	DATE

ESTIMATED QUANTITIES (BASED ON 75 SQ YD PER ENTRANCE)	AGGREGATE SHOULDER	CURB & GUTTER
HMA SURFACE COURSE @ 1/2"	7 TON	7 TON
BUTT JOINT FOR ENTRANCE RESURFACING	20 FT	45 FT
TOPSOIL, FURNISH & PLACE, 4" SEEDING, CLASS 2A, EROSION CONTROL BLANKET	10 SQ YD	10 SQ YD
BITUMINOUS MATERIALS (PRIME COAT)	12 GAL	12 GAL

REVISIONS / REMARKS		DATE	BY	SURVEYOR:
NO.	DESCRIPTION			DSGNR/LIAISON:
				PLOTTED BY: hdsxs 12/3/2009



FAIRFIELD ROAD RESURFACING 2009



FAIRFIELD RD. RESURFACING

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH 49	113	08-00999-01-RS	58	60

FILE NAME: Y:\dgn\2009 Resurfacing (Consultant Job)\Fairfield Rd - IL Rte 176 to Old McHenry Rd\FinalPlans and Qty\Detail-Sheet 6.dgn