

SUMMARY OF QUANTITIES				1000-2A ROADWAY 80% HPP 20% STATE	Y031-1F SIGNALS 80% HPP 20% STATE	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION	1000-2A ROADWAY NON-PART 100% CITY OF EVANSTON (LOCAL FUNDS)
CODE NO	PAY ITEM	UNIT	QUANTITY				
44000100	PAVEMENT REMOVAL	SQ YD	7,690	7,690			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	19,126	19,126			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	723	723			
44000600	SIDEWALK REMOVAL	SQ FT	20,046	20,046			
44001900	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	9,978	9,978			
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	14	14			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	183	183			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	52	52			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	1,919	1,919			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,150	4,150			
54219202	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 48" RISER	EACH	1	1			
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	82	82			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	20	20			
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	165	165			
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	984	984			
55100200	STORM SEWER REMOVAL 6"	FOOT	6	6			
55100300	STORM SEWER REMOVAL 8"	FOOT	120	120			
55100400	STORM SEWER REMOVAL 10"	FOOT	18	18			
55100500	STORM SEWER REMOVAL 12"	FOOT	18	18			
55100800	STORM SEWER REMOVAL 16"	FOOT	6	6			
*56300300	ADJUSTING WATER SERVICE LINES	FOOT	15	15			
*56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	5	5			
*56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	1			
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	10	10			
60200305	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	21	21			
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	2	2			
60207105	CATCH BASINS, TYPE C, TYPE 3 FRAME AND GRATE	EACH	2	2			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5			
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	8	8			
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	15	15			
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	2	2			

• SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED - CEC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SHERIDAN ROAD /FOREST AVENUE SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -- CEC	REVISED -			2865	08-00250-02-PV	COOK	79	5	
	PLOT SCALE = #SCALE#	CHECKED - DWB	REVISED -			SHEET NO. 2 OF 5 SHEETS STA. TO STA.					
	PLOT DATE = #DATE#	DATE - 04/09/2010	REVISED -			FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT CONTRACT NO. 63417					