

SUMMARY OF QUANTITIES

LOCATION OF WORK				ARA	STP - LAPP	TOTAL
				ARMITAGE AVE. 100% FED.	ARMITAGE AVE. 80% FED. 20% LOCAL	ARMITAGE AVE.
FUNDING SOURCE				ARA	STP	
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
ITEM #	ITEM	UNIT	1000	1000	1000	
	20101200	TREE ROOT PRUNING	EACH	0	10	10
	28000510	INLET FILTERS	EACH	0	43	43
	31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	175	25	200
	35800200	AGGREGATE BASE REPAIR	TON	0	20	20
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	0	400	400
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1690	40	1730
	40600300	AGGREGATE (PRIME COAT)	TON	30	5	35
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1455	75	1530
	40600895	CONSTRUCTING TEST STRIP	EACH	1	0	1
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	225	25	250
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1860	85	1945
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	75	10	85
~	42300720	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH, SPECIAL	SQ YD	25	25	50
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3500	0	3500
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	925	50	975
	42400800	DETECTABLE WARNINGS	SQ FT	340	0	340
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	16900	400	17300
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	975	50	1025
	44000600	SIDEWALK REMOVAL	SQ FT	4475	0	4475
~	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1660	0	1660
	44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	75	315	390
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	75	315	390
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	75	315	390
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	75	315	390
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	16900	400	17300
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	0	1
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	0	1
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	4	5
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	4	5
	67100100	MOBILIZATION	L SUM	1	0	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0	1
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72.8	0	72.8
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1575	75	1650
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	235	15	250
~	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0	1
~	Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	19	0	19
~	Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	28	0	28

~ INDICATES SPECIAL PROVISION

* INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME = EDTODA	DESIGNED - AMP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N:\NORTHLAKE\940032\0103\Civil\qae.dwg		DRAWN - EDT	REVISED -						1358	09-00073-00-RS	COOK	14	3
		CHECKED - MEW	REVISED -						CONTRACT NO. 63454				
		DATE - 11/12/09	REVISED -						ILLINOIS FED. AID PROJECT				