

## SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000 TOTAL QUANTITY
21101610	TOPSOIL FURNISH AND PLACE, 3"	SQ YD	350
25200100	SODDING	SQ YD	350
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,000
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	50
⊙ 40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	435
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	175
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,150
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5
42101300	PROTECTIVE COAT	SQ YD	200
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	20
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	180
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,500
42400800	DETECTABLE WARNINGS	SQ FT	40
⊙ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10,000
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	200
44000600	SIDEWALK REMOVAL	SQ FT	2,500
⊙ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	450
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	20
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	50
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	50
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	300
⊙ 60213800	RESTRICTED DEPTH CATCH BASINS, 4' DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	10
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4
⊙ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	500
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	400
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100
⊙ Z0004910	HOT-MIX ASPHALT FOR PATCHING POTHoles (HOT MIX)	TON	5

\* DENOTES SPECIALTY ITEM  
 ⊙ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\83809245 - Gardner Rd Resurf (APP)\Quantities-GardnerRd.dwg Mar 29, 2010 - 3:09pm

<b>HANCOCK</b> ENGINEERING ♦ Civil Engineers ♦ Municipal Consultants ♦ Established 1911	USER NAME --	DESIGNED -- TG	REVISED --	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE --	CHECKED -- DT	REVISED --			1005	09-00075-00-RS	COOK	11	3
PLOT DATE --	DATE -- 03/26/10	REVISED --		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	CONTRACT NO. 63458		
						FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT M-9003(578)				