


DEMOLITION PLAN NOTES:

1. REMOVE SIGN PANEL ASSEMBLY - TYPE A OR TYPE B, REMOVE SIGN PANEL - TYPE 1 - ALL EXISTING SIGN PANELS TO BE REMOVED AND CLEANED. SEE DETAIL 4, SHEET 21, THE SIGN SCHEDULE AND PLANS.
2. REMOVE SIGN PANEL - TYPE 1 - SIGNS ATTACHED TO LIGHTPOLES AND TRAFFIC POSTS TO BE REMOVED AND CLEANED. SEE DETAIL 4, SHEET 21, THE SIGN SCHEDULE AND PLANS.
2. BUS SHELTER REMOVE AND RELOCATE
3. TREE REMOVAL (6 TO 15 UNITS)
4. CONCRETE REMOVAL
5. REMOVE TEMPORARY WOOD POLE
6. REMOVE TIMBER RETAINING WALL (AVG. EXPOSED HEIGHT 2.25')
7. EARTH EXCAVATION
8. SOD STRIPPING, 2" DEPTH
9. RETAINING WALL REMOVAL
10. SELECTIVE CLEARING
11. SIGN REMOVAL, SPECIAL
12. TREE TRANSPLANT
13. PERIMETER EROSION BARRIER

LEGEND

- EXISTING SHADE TREE
- EXISTING EVERGREEN TREE
- EXISTING SHRUB
- EXISTING HEDGE/TREE LINE
- EXISTING OVERHEAD ELEC LINES
- EXISTING SIGN
- SELECTIVE CLEARING
- EXISTING GAS LINE
- EXISTING SANITARY SEWER
- EXISTING STORM SEWER
- EXISTING WATER MAIN
- EXISTING OVERHEAD METRA LINE
- EXISTING UNDERGROUND COMCAST LINE
- EXISTING UNDERGROUND ELEC LINE
- EXISTING RAILROAD LINE
- CONCRETE REMOVAL
- PERIMETER EROSION BARRIER



FILE NAME = ex. cond demo plan - 5

USER NAME =	DESIGNED -- BCL/RJA	REVISED --
PLOT SCALE =	CHECKED -- KLG	REVISED --
PLOT DATE = ####	DRAWN -- RJA	REVISED --
	CHECKED -- BCL	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EXISTING SIGN INVENTORY / DEMOLITION PLAN

SCALE: 1"= 20' SHEET NO. 5 OF 24 SHEETS STA. 0+00 TO STA. 8+00

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2843	08-00124-00-LS	COOK	24	5
CONTRACT NO. 63463				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				