

PAVEMENT SCHEDULE SHOULDERS

LOCATION	REMARKS	40600200		40600300		40603310		48100100		48203011		63500310		64200105		X0322729		MATERIAL TRANSFER DEVICE		
		SHOULDERS		SHOULDERS		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE COURSE MIX "C" N50		AGGREGATE SHOULDERS, TYPE A	HMA SHOULDERS 3 1/2"		REMAND REINSTALL DELINEATORS EACH	SHOULDER RUMBLE STRIPS						
		LENGTH	WIDTH	AREA				TON	TON		TON	TON		TON	TON	FOOT	TON			
STA TO STA		FT	FT	FT	SQ YD	SQ YD	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE		
North Bound																				
McGirr Road to Ogle County																				
1087 + 62 - 1177 + 76		9013.8	6	10	6009	10015	5.16	8.59	27.04	45.07	505	841	1283	862	6009	10015	23	9014	9014	2804
1177 + 76 - 1186 + 13	See Structure Plans	1837	6	10	1225	2041									5					
1196 + 13 - 1198 + 32	Perry Road - Ramp Opening	218.8	6	6 & Var	146	245	0.13		0.66		12		31		146		1	219		
1198 + 32 - 1201 + 95	Perry Rd - Ramp Gore	363.3	6	Var	242	411	0.21		1.09		20		52		242		1	363		
1201 + 95 - 1214 + 17	Perry Rd Between Ramps	1221.4	6	8	814	1086	0.70	0.93	3.66	4.89	68	91	174	117	814	1086	3	1221	1221	304
1214 + 17 - 1216 + 18	Perry Rd - Ramp Gore	201.8	6	Var	135	117	0.12		0.61		11		29		135		1	202		
1216 + 18 - 1226 + 0	Perry Rd - Ramp Opening	981.7	6	6 & Var	654	678	0.56		2.95		55		140		654		2	982		
1226 + 0 - 1351 + 66		12566	6	10	8377	13962	7.19	11.98	37.70	62.83	704	1173	1789	1202	8377	13962	31	12566	12566	3909
1351 + 66 - 1353 + 86	Tie into Ogle Co 5" Overlay	220	6	10	147	244	0.13	0.21	0.66	1.10	12	21	31	21	147	244	1	220	220	68
MEDIAN CROSSOVERS																				
MEDIAN AREA																				
1163 + 21			4	4	205		0.12		0.62		17		14		205					57
1248 + 92			4	4	205		0.12		0.62		17		14		205					57
SUBTOTAL							14.4	21.7	75.6	113.9	1423	2126	3556	2202	16935	25308	67	24787	23021	7201
							36.1		189.6		3549		5759		42242			47808		

South Bound																				
LaSalle County to McGirr Road																				
320 + 50 - 322 + 50	LaSalle County - 40:1 Taper	200	6	10	133	222	0.11	0.19	0.60	1.00	11	19	28	19	133	222	1	200	200	62
322 + 50 - 338 + 84	LaSalle County	1633.9	6	10	1089	1815	0.93	1.56	4.90	8.17	91	152	233	156	1089	1815	4	1634	1634	508
338 + 84 - 495 + 41		15657.1	6	10	10438	17397	8.96	14.93	46.97	78.29	877	1461	2229	1498	10438	17397	39	15657	15657	4871
495 + 41 - 499 + 31	Shady Oaks - Profile Adjustment	390	6	10	260	433	0.22	0.37	1.17	1.95	22	36	56	37	260	433	1	390	390	121
499 + 31 - 600 + 0		10069	6	10	6713	11188	5.76	9.60	30.21	50.35	564	940	1433	963	6713	11188	25	10069	10069	3133
600 + 0 - 608 + 48	Chicago Rd - Ramp Opening	848	6	6 & Var	565	660	0.49		2.54		47		121		565		2	848		
608 + 48 - 612 + 68	Chicago Rd - Ramp Gore	420.1	6	Var	280	215	0.24		1.26		24		60		280		1	420		
612 + 68 - 638 + 85		2596.9	6	10	1731	2885	1.49	2.48	7.79	12.98	145	242	370	248	1731	2885	6	2597	2597	808
638 + 65 - 642 + 36	Chicago Rd - Ramp Gore	370.9	6	Var	247	370	0.21		1.11		21		53		247		1	371		
642 + 36 - 645 + 25	Chicago Rd - Ramp Opening	288.9	6	6 & Var	193	205	0.17		0.87		16		41		193		1	289		
645 + 25 - 719 + 38		7413.5	6	10	4942	8237	4.24	7.07	22.24	37.07	415	692	1055	709	4942	8237	19	7414	7414	2306
719 + 38 - 741 + 26	Rest Area - Ramp Opening	2187.7	6	6 & Var	1458	1942	1.25		6.56		123		311		1458		5	2188		
741 + 26 - 744 + 88	Rest Area - Ramp Gore	361.8	6	Var	241	235	0.21		1.09		20		52		241		1	362		
744 + 88 - 771 + 15		2626.8	6	10	1751	2919	1.50	2.50	7.88	13.13	147	245	374	251	1751	2919	7	2627	2627	817
771 + 15 - 775 + 9	Rest Area - Ramp Gore	383.9	6	Var	263	424	0.23		1.18		22		56		263		1	384		
775 + 9 - 777 + 77	Rest Area - Ramp Opening	268	6	6 & Var	179	351	0.15		0.80		15		38		179		1	268		
775 + 9 - 852 + 97		7788	6	10	5192	8653	4.45	7.42	23.36	38.94	436	727	1109	745	5192	8653	19	7788	7788	2423
852 + 97 - 862 + 43	US 30 - Ramp Opening	946.4	6	6 & Var	631	210	0.54		2.84		53		135		631		2	946		

REVISED
5-27-2010
SHEET

FILE NAME =	USER NAME = stringer_jm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PAVEMENT SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			39	(103-1, 103-2)RS	LEE	313	33	
		CHECKED -	REVISED -			CONTRACT NO. 64E97					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
PLOT SCALE = 1/80,000' / IN.		PLOT DATE = Thu May 27 13:38:55 2010		SCALE:		SHEET NO. OF SHEETS STA. TO STA.					