

# PAVEMENT SCHEDULE RAMPS

LOCATION	REMARKS	40600200		40600300		40600400		40600645		40600855		40600985		40603245		40603310		40603370		40603575		48100100		48203011		63500310		X0322729	
		RAMP AREA	RAMP SHOULDER AREA		BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	MIX FOR CRACKS JOINTS & FLANGEWAYS	LEVEL BIND (MM) N90	POLY HMA LEVEL BINDER (MM) N105	PCC SURFACE REMOVAL BUTT JOINT	POLY HMA BINDER COURSE IL-19.0, N105	HMA SURFACE COURSE MIX "C" N50		HMA SURF CSE MIX "E" N90	POLY HMA SURFACE COURSE MIX "E" N105	AGGREGATE SHOULDERS, TYPE A		HMA SHOULDERS 3 1/2"		REMAND REINSTALL DELINEATORS		MATERIAL TRANSFER DEVICE							
			SQ YD	INSIDE								OUTSIDE	TON			TON	TON	TON	TON	TON	TON		TON	TON	TON	TON	TON	TON	TON
RAMP D																													
RAMP OPENING AREA	5"	590		362	0.82	4.28	1.35		41.3		74								53										168
RAMP TRANSITION AREA	5" - 2.5"	347	2	145	0.28	1.48	0.57		1.2		15	0.2	12.2						31										47
RAMP AREA	2.5"	2824	744	1098	2.14	11.24	4.40	158.1				187.5	276.7	237									176	176			6	4	395
RAMP TAPER AREA	2.5" - 0"	268	16	52	0.17	0.91	0.14	4.5				168											6	6					27
<b>LaSalle County to McGirr Road</b>			TOTAL		36.6	192.0	78.7	1234.2	1018.5	1228	1993	1645.1	2451.2	1950	1858	1729	3541	353	5283	53	38	7850							
												4096		5270		5636		91											

**McGirr Road to Ogle County**

PERRY ROAD																																
RAMP E																																
RAMP OPENING AREA	5"	612		133	0.64	3.35	1.38		43		77			11.2					55							69		133			175	
RAMP TRANSITION AREA	5" - 2.5"	363	11	137	0.29	1.53	0.57		1.3		16	0.9	11.5						32	3	28	11	137			1				50		
RAMP AREA	2.5"	3146	753	1017	2.31	12.09	4.76	176				189.8	256.3	264									191	191				7	4	440		
RAMP TAPER AREA	2.5" - 0"	90	26	34	0.07	0.36	0.14	1.5				75											6	6						9		
RAMP F																																
RAMP OPENING AREA	5"	363		95	0.39	2.06	0.57		25		46			8.0					32							29		95			104	
RAMP TRANSITION AREA	5" - 2.5"	378	46	103	0.30	1.58	0.57		1.3		17	3.9	8.7						34	11	28	46	103			1				52		
RAMP AREA	2.5"	2096	506	615	1.52	7.97	2.97	117				127.5	155.0	176									119	119				4	4	283		
RAMP TAPER AREA	2.5" - 0"	90	22	30	0.07	0.35	0.14	1.5				71											6	6						9		
RAMP G																																
RAMP OPENING AREA	5"	610		133	0.64	3.34	1.19		43		77			11.2					54									133			174	
RAMP TRANSITION AREA	5" - 2.5"	361	18	129	0.29	1.52	0.57		1.3		16	1.5	10.8						32	3	28	18	129			1				49		
RAMP AREA	2.5"	3419	858	1092	2.51	13.18	5.13	191				216.2	275.2	287									206	206				7	4	479		
RAMP TAPER AREA	2.5" - 0"	91	22	33	0.07	0.36	0.14	1.5				73											6	6						9		
RAMP H																																
RAMP OPENING AREA	5"	1116		133	1.07	5.62	2.88		78		141			11.2													144		133			318
RAMP TRANSITION AREA	5" - 2.5"	379	95	110	0.33	1.75	0.57		1.3		17	8.0	9.2						34	23	28	95	110			1				52		
RAMP AREA	2.5"	3508	838	1168	2.58	13.53	5.37	196				211.2	294.3	295									215	215				8	4	491		
RAMP TAPER AREA	2.5" - 0"	92	23	31	0.07	0.36	0.14	1.5				73											6	6						9		
<b>McGirr Road to Ogle County</b>			TOTAL		13.1	69.0	27.1	688	194	292	408	782	1095	1053	373	794	1189	170	973	29	16	2713										
												1877		1963		1143		45														
<b>GRANDTOTAL</b>		49.7	261.0	105.8	1922	1213	1520	2399	5973	3003	2029	7233	6779	136	10563																	

**REVISED**  
**5-27-2010**  
**SHEET**

NOTE: RAMP AREA & RAMP TAPER HMA SHOULDER INCLUDES AN EXTRA 2" FOR LOW SHOULDERS OR MISSING EXISTING SHOULDERS

FILE NAME =	USER NAME = stringerjm	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>I-39</b> <b>PAVEMENT SCHEDULE</b>	DRAWN -	REVISED -	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pavework\PIWIDOT\STRINGERJM\d0149531\02058091-sh1-pm.dgn		CHECKED -	REVISED -			39	LEE	313	37		
PLOT SCALE = 100.0000' / 1"		DATE -	REVISED -			CONTRACT NO. 64E97					
PLOT DATE = Thu May 27 13:38:56 2010						[ILLINOIS] FED. AID PROJECT					