

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	LASALLE TO MCGIRR 100% State 1000	MCGIRR TO OGLE 100% State 1000	Bridge Repair 100% State \$FTY-2A
X7030068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	85	85		
X7030070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	453507	332969	120538	
X7030074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	51735	38386	13349	
X7030076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	11704	9037	2667	
X7030078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	1870	1410	460	
X7030090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	384	288	96	
Z0005400	BREAKER-RUN CRUSHED STONE	TON	2822	2117	705	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	6040			6040
Z0010555	DITCH CLEANING	FOOT	362			362
Z0015500	DEBRIS REMOVAL	L SUM	1	1		
Z0017100	DOWEL BARS	EACH	1372	1008	364	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	68			68
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	87			87

**\* SPECIALTY ITEMS**

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-39 SUMMARY OF QUANTITIES</b>	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cs:\pwork\pwork\dot\dssdd\0149531\0205809-shr-S00.dgn		DRAWN -	REVISED -			39	(103-1, 103-2)RS	LEE	313	17
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = Mon Mar 29 13:27:59 2010	DATE -	REVISED -		SCALE:				SHEET NO. OF SHEETS	STA. TO STA.
										ILLINOIS FED. AID PROJECT CONTRACT NO. 64E97