

PAVEMENT SCHEDULE PROFILE ADJUSTMENT

LOCATION	REMARKS	31100910		31200500		35100500		42100300		42100900		44002100		44004250		48300300		60100060		60107600		60108100		
		STA TO STA	MAINLINE	SHOULDERS		SUB GRAN MAT TYPE A 12" SQ YD	STABILIZED SUB-BASE HMA 4" SQ YD	AGGREGATE BASE COURSE TYPE A, 6" SQ YD		CONT. REINF PCC PAV'T 10" SQ YD	PAV'T REINF 10" SQ YD	CONT. REINF PCC PAV'T REM SQ YD	PAVED SHOULDER REMOVAL SQ YD		PCC SHOULDERS 8" SQ YD		CONCRETE HEADWALL FOR PIPE UNDERDRAIN EACH		PIPE UNDERDRAINS 4" FOOT		PIPE UNDERDRAINS 4" (SPECIAL) FOOT			
			LENGTH FT	AREA SQ YD	WIDTH FT FT			INSIDE	OUTSIDE				INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
North Bound																								
LaSalle County to McGirr Road																								
496 + 11 - 499 + 21	Shady Oaks - Profile Adjustment	310	827	6	10	937	937	207	344	827	827	827	207	344	207	344	2	2	310	310	26	34		
713 + 16 - 720 + 72	Beemerville - Profile Adjustment	756.4	2017	6	10	2286	2286	504	840	2017	2017	2017	504	840	504	840	2	2	756	756	26	34		
						3223	3223	711	1185	2844	2844	2844	711	1185	711	1185	4	4	1066	1066	52	68		
								1896						1896		1896		8		2132		120		
South Bound																								
LaSalle County to McGirr Road																								
495 + 41 - 499 + 31	Shady Oaks - Profile Adjustment	390	1040	6	10	1179	1179	260	433	1040	1040	1040	260	433	260	433	2	2	390	390	26	34		
								693						693		693		4		780		60		
LaSalle County to McGirr Road						SUBTOTAL		4402	4402	971	1618	3884	3884	3884	971	1618	971	1618	6	6	1456	1456	78	102
								2589						2589		2589		12		2912		180		
McGirr Road to Ogle County																								
1086 + 13 - 1089 + 23	Mc Girr - Profile Adjustment	310	827	6	10	937	937	207	344	827	827	827	207	344	207	344	2	2	310	310	26	34		
								551						551		551		4		620		60		
GRANDTOTAL						5339	5339	3140	4711	4711	4711	4711	3140	3140	3140	3140	16	16	3532	3532	240	240		