

PAVEMENT MARKING SCHEDULE MAINLINE

LOCATION STA TO STA	REMARKS	LENGTH FT	70300100			70300220		70300240		70300250		70300260		70301000			78008300		78008310		78008330		78008340		78008350			
			SHORT-TERM PAVEMENT MARKING			TEMPORARY PAVT MARKING - LINE 4"		TEMPORARY PAVT MARKING - LINE 6"		TEMPORARY PAVT MARKING - LINE 8"		TEMPORARY PAVT MARKING - LINE 12"		WORK ZONE PAVEMENT MARKING REMOVAL			POLYUREA PAVT MARKING TY II LETTERS & SYMBOLS		POLYUREA PAVT MARKING TY II - LINE 4"		POLYUREA PAVT MARKING TY II - LINE 6"		POLYUREA PAVT MARKING TY II - LINE 8"		POLYUREA PAVT MARKING TY II - LINE 12"			
			FOOT			FOOT		FOOT		FOOT		FOOT		SQ FT			SQ FT		FOOT		FOOT		FOOT		FOOT			
			INSIDE	CENTER	OUTSIDE	INSIDE	OUTSIDE	CENTERLINE	GORE	DIAGONALS	INSIDE	CENTER	OUTSIDE				INSIDE	OUTSIDE	CENTERLINE	GORE	DIAGONALS							
North Bound						YELLOW	WHITE	WHITE	WHITE	WHITE							YELLOW	WHITE	WHITE	WHITE	WHITE							
LaSalle County to McGirr Road																												
320 + 50 - 322 + 50	LaSalle County - 40:1 Taper	200	24	24	24	400	400	100						141	58	141				200	200	50						
322 + 50 - 338 + 84	LaSalle County	1634	196	196	196	3268	3268	817						1155	474	1155				1634	1634	408						
338 + 84 - 496 + 11		15727	1887	1887	1887	31454	31454	7864						11114	4561	11114				15727	15727	3932						
496 + 11 - 499 + 21	Shady Oaks - Profile Adjustment	310	37	37	37	620	620	155						219	90	219				310	310	78						
499 + 21 - 605 + 68		10647	1278	1278	1278	21294	21294	5324						7524	3088	7524				10647	10647	2662						
605 + 68 - 608 + 68	Chicago Rd - Ramp B Opening	300	36	36		601		150						212	87					300		75						
608 + 68 - 612 + 36	Chicago Rd - Ramp B Gore	368	44	44		735		184	1471	240				260	107	1220				368		92	735	120				
612 + 36 - 638 + 66		2630	316	316	316	5259	5259	1315						1858	763	1858				2630	2630	657						
638 + 66 - 642 + 83	Chicago Rd - Ramp C Gore	418	50	50		835		209	1671					295	121	1114				418		104	835					
642 + 83 - 650 + 0	Chicago Rd - Ramp C Opening	717	36	86		1433		358						506	208					717		179						
650 + 0 - 713 + 16		6316	758	758	758	12632	12632	3158						4463	1832	4463				6316	6316	1579						
713 + 16 - 720 + 72	Beemerville - Profile Adjustment	756	91	91	91	1513	1513	378						535	219	535				756	756	189						
720 + 72 - 723 + 45	Rest Area - Ramp B Opening	273	33	33		545		136						193	79					273		68						
723 + 45 - 727 + 33	Rest Area - Ramp B Gore	388	47	47		775		194	1551	240				274	112	1274				388		97	775	110				
727 + 33 - 752 + 25		2492	299	299	299	4985	4985	1246						1761	723	1761				2492	2492	623						
752 + 25 - 755 + 86	Rest Area - Ramp C Gore	361	43	43		723		181	1446					255	105	964				361		90	723					
755 + 86 - 769 + 35	Rest Area - Ramp C Opening	1349	162	162		2697		674						953	391					1349		337						
769 + 35 - 856 + 22		8687	1042	1042	1042	17373	17373	4343						6139	2519	6139				8687	8687	2172						
856 + 22 - 858 + 78	US 30 - Ramp B Opening	256	31	31		513		128						181	74					256		64						
858 + 78 - 862 + 97	US 30 - Ramp B Gore	419	50	50		838		209	1676	240				296	121	1357				419		105	838	130				
862 + 97 - 874 + 91	160' Taper & Removal at Wide Flange Beam	1194	143	143	143	2388	2388	597						844	346	844				1194	1194	299						
874 + 91 - 879 + 26	US 30 See Structure Plans	435	52	52	52	870	870	218						307	126	307				435	435	109						
879 + 26 - 889 + 38	160' Taper & Removal at Wide Flange Beam	1012	121	121	121	2025	2025	506						715	294	715				1012	1012	253						
889 + 38 - 891 + 73	US 30 - Ramp C Gore	235	28	28		469		117	938					166	68	626				235		59	469					
891 + 73 - 901 + 33	US 30 - Ramp C Opening	960	115	115		1920		480						678	278					960		240						
901 + 33 - 1087 + 62		18629	2236	2236	2236	37259	37259	9315						13165	5403	13165				18629	18629	4657						
AERIAL SPEED CHECK			CONTACT STATE POLICE FOR LOCATION																									
LaSalle County to McGirr Road			9205	9205	8480	153424	141340	38356	8752	720	54210	22247	56495	40.5	76712	70670	19178	4376	360									
			26890			294764						132952			147382													

NOTE: SHORT-TERM AND TEMPORARY PAVEMENT MARKING ASSUMES 2 APPLICATIONS

FILE NAME =	USER NAME = dossed	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PAVEMENT MARKING SCHEDULE	F.A.I. RTE. =	SECTION =	COUNTY =	TOTAL SHEETS =	SHEET NO. =	
es:\pwork\pwork\dossed\0149531\020588\9-sh-t-pm.dgn		DRAWN -	REVISED -			39	(103-1, 103-2)RS	LEE	313	38	
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 64E97		
PLOT DATE = Mon Mar 29 11:16:51 2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					