

# PAVEMENT MARKING SCHEDULE MAINLINE

LOCATION	REMARKS	LENGTH FT	X7030068	X7030070	X7030074	X7030076	X7030078	78100100	78100105	78300200	
			GROOVING FOR RECS D PAVT MARK LETTER # SYMB	GROOVING FOR RECESSED PAVT MARKING 5"	GROOVING FOR RECESSED PAVT MARKING 7"	GROOVING FOR RECESSED PAVT MARKING 9"	GROOVING FOR RECESSED PAVT MARKING 13"	RAISED REFLECTIVE PAVT MARKER	RAISED REFLECTIVE PAVT MARKER BR	RAISED REFL PAVT MARKER REMOVAL	
			SQ FT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	
<b>North Bound</b>			INSIDE	INSIDE	OUTSIDE	CENTERLINE	GORE	DIAGONALS		ASSUMING NO MISSING REFL	
<b>McGirr Road to Ogle County</b>											
1087 + 62 - 1177 + 76	160' Taper & Removal at Wide Flange Beam	9014		9014	9014	2253			113	113	
1177 + 76 - 1196 + 13	See Structure Plans	1837		1837	1837	459			23	23	
1196 + 13 - 1198 + 32	Perry Road - Ramp G Opening 160' Taper & Rem at W Flange Beam	219		219		55			14	14	
1198 + 32 - 1201 + 95	Perry Rd - Ramp G Gore	363		363		91	727	120	41	41	
1201 + 95 - 1214 + 17	Perry Rd Between Ramps	1221		1221	1221	305			15	15	
1214 + 17 - 1216 + 18	Perry Rd - Ramp H Gore	202		202		50	404		3	3	
1216 + 18 - 1226 + 0	Perry Rd - Ramp H Opening	982		982		245			12	12	
1226 + 0 - 1351 + 66		12566		12566	12566	3142			157	157	
1351 + 66 - 1353 + 86	Tie into Ogle Co 5" Overlay	220		220	220	55			3	3	
<b>McGirr Road to Ogle County</b>			0	26624	24858	6656	1130	120	357	23	380
				51482							

South Bound										
LaSalle County to McGirr Road										
320 + 50 - 322 + 50	LaSalle County - 40:1 Taper	200		200	200	50			3	3
322 + 50 - 338 + 84	LaSalle County	1634		1634	1634	408			20	20
338 + 84 - 495 + 41		15657		15657	15657	3914			196	196
495 + 41 - 499 + 31	Shady Oaks - Profile Adjustment	390		390	390	98			5	5
499 + 31 - 600 + 0		10069		10069	10069	2517			126	126
600 + 0 - 608 + 48	Chicago Rd - Ramp A Opening	848		848		212			11	11
608 + 48 - 612 + 68	Chicago Rd - Ramp A Gore	420		420		105	840		5	5
612 + 68 - 638 + 65		2597		2597	2597	649			162	162
638 + 65 - 642 + 36	Chicago Rd - Ramp D Gore	371		371		93	742	120	42	42
642 + 36 - 645 + 25	Chicago Rd - Ramp D Opening	289		289		72			4	4
645 + 25 - 719 + 38		7414		7414	7414	1853			93	93
719 + 38 - 741 + 26	Rest Area - Ramp A Opening	2188		2188		547			27	27
741 + 26 - 744 + 88	Rest Area - Ramp A Gore	362		362		90	724		5	5
744 + 88 - 771 + 15		2627		2627	2627	657			164	164
771 + 15 - 775 + 9	Rest Area - Ramp D Gore	394		394		98	788	140	44	44
775 + 9 - 777 + 77	Rest Area - Ramp D Opening	268		268		67			3	3
775 + 9 - 852 + 97		7788		7788	7788	1947			97	97
852 + 97 - 862 + 43	US 30 - Ramp A Opening	946		946		237			12	12

NOTE: SHORT-TERM AND TEMPORARY PAVEMENT MARKING ASSUMES 2 APPLICATIONS

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-39 PAVEMENT MARKING SCHEDULE</b>	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
01\pwork\pwork\dssdd\0149531\020589	9-sh-t-pm.dgn	DRAWN -	REVISED -			39	(103-1, 103-2)RS	LEE	313	41	
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE:		SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 64E97	
	PLOT DATE = Fri Mar 26 08:03:58 2010	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					