SCHEDULE OF QUANTITIES

25100630	EROSION CONTROL BLANKET				28000305	TEMPORARY	DITCH CHECKS		
	SQ YD	LOCATION	OFFSET	<u>REMARKS</u>		<u>FOOT</u>	LOCATION	<u>OFFSET</u>	REMARKS
		LASALLE CO TO MCGIRR RD					LASALLE CO TO MCGIRR RD		ESTIMATED
	2500	US 30 GUARDRAIL				3500	AS DIRECTED BY RE/TE		
	7500	7500 GRADING AND SHAPING MEDIAN CROSSOVERS					MCGIRR RD TO OGLE CO		
	25000	25000 GRADING AND SHAPING DITCHES		GORE AREAS & INLETS		1500	AS DIRECTED BY RE/TE		
	35000	SUBTOTAL				5000 TO	OTAL		
		MCGIRR RD TO OGLE CO							
	2000	2000 STRUCTURE GUARDRAIL		STEWARD CREEK TO PERRY ROAD					
	2000	2000 GRADING AND SHAPING MEDIAN CROSSOVERS			28000400	PERIMETER E	ROSION BARRIER		
	4500 GRADING AND SHAPING DITCHES		GORE AREAS & INLETS		FOOT	LOCATION	<u>OFFSET</u>	<u>REMARKS</u>	
	8500	_SUBTOTAL					LASALLE CO TO MCGIRR RD		ESTIMATED
	43500	TOTAL				25000	AS DIRECTED BY RE/TE		
							MCGIRR RD TO OGLE CO		
						25000	AS DIRECTED BY RE/TE		
25100900	TURF REII	NFORCEMENT MAT				50000 TO	OTAL		
	SQ YD	LOCATION	OFFSET	<u>REMARKS</u>					
		LASALLE CO TO MCGIRR RD		ESTIMATED					
	278	360+40 TO 361+40	LT	100' X 25'	28000500	INLET AND PI	PE PROTECTION		
	556	728+86 TO 730+86	RT	200' X 25'		EACH	LOCATION	OFFSET	REMARKS
	556	916+09 TO 918+09	RT	200' X 25'			LASALLE CO TO MCGIRR RD		
	2000	988+50	RT	CHANNEL 300' X 60'		1	347+13		MEDIAN
	3390	TOTAL				1	360+23		MEDIAN
						1	689+92		MEDIAN
						4	AS DIRECTED BY RE/TE		
28000250						7 SI	UBTOTAL		
	POUND	LOCATION	OFFSET	REMARKS		_	MCGIRR RD TO OGLE CO		
		LASALLE CO TO MCGIRR RD		8 APPLICATIONS IF APPLICABLE		3	AS DIRECTED BY RE/TE		
	208	SHADY OAKS		APPLICATION RATE = 100 LB/ACRE		10T0	DTAL		
	285	BEEMERVILLE							
	352	US 30	150						
	3260	GRADING AND SHAPING DITCH	IES						
	4105								
	0	MCGIRR RD TO OGLE CO							
	8 1040	MCGIRR STRUCTURES							
	2204	GRADING AND SHAPING DITCH	IFS						
	3252 SUBTOTAL								
	7357 TOTAL								
	1001								

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DESIGNED -

CHECKED -

DRAWN

DATE

o:\pw_work\PWIDOT\DOSSDD\d0149531\D2058<mark>0</mark>9-sht-schedule.dgn

PLOT SCALE = 50.0000 '/ IN.

PLOT DATE = Mon Mar 29 11:31:39 2010

REVISED

REVISED

REVISED

REVISED

COUNTY TOTAL SHEETS NO.

LEE 313 56

CONTRACT NO. 64E97

SECTION

(103-1, 103-2)RS

SCHEDULE OF QUANTITIES

TO STA.

SHEET NO. OF SHEETS STA.

SCALE: