

# SCHEDULE OF QUANTITIES

44004250 PAVED SHOULDER REMOVAL

44002100 CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL

	SQ YD	LOCATION	OFFSET	REMARKS	SQ YD	LOCATION	OFFSET	REMARKS	
		<u>LASALLE CO TO MCGIRR RD</u>				<u>LASALLE CO TO MCGIRR RD</u>			
		<u>STEWARD CREEK</u>				<u>US 30</u>			
80	80	874+86 TO 875+16	SB LANES		131	874+86 TO 876+04	SB LT		
80	80	874+90 TO 875+20	NB LANES		79	874+86 TO 876+04	SB MEDIAN		
80	80	878+95 TO 879+25	NB LANES		79	874+90 TO 876+08	NB MEDIAN		
80	80	878+98 TO 879+28	SB LANES		131	874+90 TO 876+08	NB RT		
	320	SUBTOTAL			10	876+15	NB MEDIAN	STAGE 1 REMOVAL	
		<u>MCGIRR RD TO OGLE CO</u>			134	878+08 TO 879+29	SB LT		
		<u>STEWARD CREEK</u>			81	878+08 TO 879+29	SB MEDIAN		
104	104	1177+30 TO 1177+69	SB LANES		76	878+12 TO 879+26	NB MEDIAN		
104	104	1177+75 TO 1178+14	NB LANES		127	878+12 TO 879+26	NB RT		
845	845	1181+83 TO 1185+00	SB LANES		848	SUBTOTAL			
824	824	1181+91 TO 1185+00	NB LANES			<u>MCGIRR RD TO OGLE CO</u>			
451	451	1185+00 TO 1186+69	SB LANES			<u>STEWARD CREEK</u>			
357	357	1185+00 TO 1186+34	NB LANES		127	1177+30 TO 1178+44	SB LT		
		<u>BNSF RR</u>			85	1177+30 TO 1178+58	SB MEDIAN		
651	651	1189+80 TO 1192+24	NB LANES		77	1177+75 TO 1178+90	NB MEDIAN		
721	721	1190+22 TO 1192+21	SB LANES		133	1177+75 TO 1178+95	NB RT		
		<u>PERRY ROAD</u>			821	1180+90 TO 1187+62	SB LT		
140	140	1195+83 TO 1196+13	SB LANES		439	1180+90 TO 1187+48	SB MEDIAN		
96	96	1195+83 TO 1196+13	NB LANES		420	1180+96 TO 1187+26	NB MEDIAN		
	4293	SUBTOTAL			735	1181+13 TO 1187+14	NB RT		
	4613	TOTAL			10	1180+95	NB MEDIAN	STAGE 1 REMOVAL	
						<u>BNSF RR</u>			
					10	1187+30	NB MEDIAN	STAGE 1 REMOVAL	
					10	1189+00	NB MEDIAN	STAGE 1 REMOVAL	
					268	1189+06 TO 1193+08	NB MEDIAN		
					491	1189+06 TO 1193+08	NB RT		
					10	1189+25	SB MEDIAN	STAGE 1 REMOVAL	
					248	1189+37 TO 1193+09	SB MEDIAN		
					205	1189+46 TO 1192+09	SB LT		
						<u>PERRY ROAD</u>			
					10	1193+35	SB MEDIAN	STAGE 1 REMOVAL	
					79	1194+94 TO 1196+13	SB LT		
					79	1194+94 TO 1196+13	SB MEDIAN		
					79	1194+94 TO 1196+13	NB MEDIAN		
					106	1194+94 TO 1196+13	NB RT		
					4442	SUBTOTAL			
					5290	TOTAL			