

SCHEDULE OF QUANTITIES

X0326682 UPGRADE EXISTING WEATHER STATION

L SUM	LOCATION	OFFSET	REMARKS
	LASALLE CO TO MCGIRR RD		
1	532+00	NB RT	SEE SPECIAL PROVISION

X0329911 GRADING AND SHAPING MEDIAN CROSSOVER

EACH	LOCATION	OFFSET	REMARKS
	LASALLE CO TO MCGIRR RD		
1	320+84		
1	456+75		
1	575+51		
1	689+49		
1	814+72		
1	917+09		
1	1047+77		
7	SUBTOTAL		
	MCGIRR RD TO OGLE CO		
1	1163+21		
1	1248+92		
2	SUBTOTAL		
9	TOTAL		

X0931400 INLET BOXES TO BE ADJUSTED (SPECIAL) - CONT.

EACH	LOCATION	OFFSET	REMARKS
	MCGIRR RD TO OGLE CO		
	Steward Creek		
1	1178+47	SB LT	
1	1178+62	SB MEDIAN	
1	1178+92	NB MEDIAN	
1	1179+06	NB RT	
1	1180+54	SB LT	
1	1181+07	NB RT	
1	1193+02	NB RT	
1	1193+02	SB LT	
	Perry Rd		
1	1195+94	SB LT	
1	1195+94	SB MEDIAN	
1	1195+94	NB MEDIAN	
1	1195+94	NB RT	
12	SUBTOTAL		
16	TOTAL		

X4210307 WIDE FLANGE BEAM TERMINAL JOINT REPAIR (SPECIAL)

EACH	LOCATION	OFFSET	REMARKS
	LASALLE CO TO MCGIRR RD		
	US 30		
1	874+87	SB LANES	
1	874+91	NB LANES	
1	878+26	NB LANES	
1	878+29	SB LANES	
4	SUBTOTAL		
	MCGIRR RD TO OGLE CO		
	Steward Creek		
1	1177+30	SB LANES	
1	1177+76	NB LANES	
	Perry Rd		
1	1196+13	SB LANES	
1	1196+13	NB LANES	
4	SUBTOTAL		
8	TOTAL		

X0931400 INLET BOXES TO BE ADJUSTED (SPECIAL)

EACH	LOCATION	OFFSET	REMARKS
	LASALLE CO TO MCGIRR RD		
	US 30		
1	878+09	SB LT	
1	878+09	SB MEDIAN	
1	878+09	NB MEDIAN	
1	878+09	NB RT	
4	SUBTOTAL		