



**TOTAL BILL OF MATERIAL**

ITEM	UNIT	QUANTITY
Stone Riprap, Class A2	Sq. Yd.	80
Approach Slab Removal	Sq. Yd.	1,127
Concrete Removal	Cu. Yd.	26.4
Slope Wall Removal	Sq. Yd.	126
Protective Shield	Sq. Yd.	722
Concrete Structures	Cu. Yd.	51.5
Concrete Superstructure	Cu. Yd.	272.2
Bridge Deck Grooving	Sq. Yd.	*1,848
Protective Coat	Sq. Yd.	*1,964
Furnishing and Erecting Structural Steel	Pound	6,130
Jack and Remove Existing Bearings	Each	24
Structural Steel Removal	Pound	1,560
Reinforcement Bars, Epoxy Coated	Pound	68,170
Bar Splicers	Each	496
Slope Wall 4 Inch	Sq. Yd.	126
Preformed Joint Strip Seal	Foot	174
Elastomeric Bearing Assembly, Type I	Each	24
Anchor Bolts, 1"	Each	48
Bridge Deck Hydro-Scarification 1/2"	Sq. Yd.	1,394
Deck Slab Repair (Full Depth, Type I)	Sq. Yd.	13
Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	4
Bridge Approach Shoulder Removal	Sq. Yd.	66
Bridge Deck Microsilica Concrete Overlay 2 3/4"	Sq. Yd.	1,394

\*Quantity includes Approach Pavement

