

SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	100% STATE SFTY-2A QUANTITY
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	18
42001300	PROTECTIVE COAT	SQ YD	109
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	44
44000700	APPROACH SLAB REMOVAL	SQ YD	74
50102400	CONCRETE REMOVAL	CU YD	67
50300225	CONCRETE STRUCTURES	CU YD	0.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7,300
50800515	BAR SPLICERS	EACH	56
52000110	PREFORMED JOINT STRIP SEAL	FOOT	82
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2
70106700	TEMPORARY RUMBLE STRIP	EACH	12
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,736
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,452
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	650
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2800
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1580
X0300130	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	18
X5080600	MECHANICAL SPLICERS	EACH	149
20030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4
20030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4

* SPECIALTY ITEM

FILE NAME = G:\BR\CADD plans\Various Counties\64G13	USER NAME = linkdj approach pavements\PLANeng.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	* (102BRM & 139BRM)			OGLE	19	2		
PLOT DATE = Tue Mar 16 08:27:22 2010	DATE -	REVISED -	CONTRACT NO. 64G13							

* FAP 17 (IL 64) & FAP 742 (IL 2)

ILLINOIS FED. AID PROJECT