

SCHEDULE OF QUANTITIES

20200100	EARTH EXCAVATION CU_YD	LOCATION MAINLINE	647 + 50	TO	654 + 00	REMARKS TEMPORARY FIELD ENTRANCE REMOVAL	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING TON	LOCATION MAINLINE	651 + 05	REMARKS PRIVATE ENTRANCE	
		LT	649 + 00					2.9	LT			
TOTAL	289.7 40.0 329.7	LT/RT					TOTAL	2.9				
20400800	FURNISHED EXCAVATION CU_YD	LOCATION MAINLINE	649 + 00	TO	654 + 00		44201359	CLASS C PATCHES, TYPE IV, 10 INCH SQ_YD	LOCATION MAINLINE	651 + 05	TO 652 + 10	REMARKS
TOTAL	120.0 120.0	LT/RT					TOTAL	303.3 303.3	LT/RT			
25100630	EROSION CONTROL BLANKET SQ_YD	LOCATION MAINLINE	649 + 00	TO	654 + 00		50100300	REMOVAL OF EXISTING STRUCTURES, NO. 1 EACH	LOCATION MAINLINE	651 + 55		REMARKS 8' X 5' BOX
TOTAL	334.1 250.1 584.2	LT RT	649 + 00	TO	654 + 00		TOTAL	1.0 1.0				
28000250	TEMPORARY EROSION CONTROL SEEDING POUND	LOCATION MAINLINE	647 + 00	TO	657 + 00		50100400	REMOVAL OF EXISTING STRUCTURES, NO. 2 EACH	LOCATION MAINLINE	651 + 35		REMARKS 36" PIPE
TOTAL	600.0 600.0	LT/RT					TOTAL	1.0 1.0				
28000305	TEMPORARY DITCH CHECKS FOOT	LOCATION MAINLINE	652 + 00	TO	652 + 50		51205200	TEMPORARY SHEET PILING SQ_FT	LOCATION MAINLINE	651 + 48	TO 654 + 84	REMARKS
TOTAL	50.0 30.0 80.0	LT RT	651 + 00	TO	651 + 20		TOTAL	2025.0 2,025.0				
28000500	INLET AND PIPE PROTECTION EACH	LOCATION MAINLINE	647 + 34				51500100	NAME PLATES EACH	LOCATION MAINLINE	651 + 35		REMARKS
TOTAL	1.0 1.0 3.0	LT LT RT	652 + 10				TOTAL	1.0 1.0				
28100107	STONE RIPRAP, CLASS A4 SQ_YD	LOCATION MAINLINE	651 + 22				54010805	PRECAST CONCRETE BOX CULVERT 8' X 5' FOOT	LOCATION MAINLINE	651 + 25	TO 652 + 00	REMARKS
TOTAL	17.8 73.0 90.8	RT LT	652 + 10				TOTAL	108.0 108.0				
28200200	FILTER FABRIC SQ_YD	LOCATION MAINLINE	651 + 22				5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY) FOOT	LOCATION MAINLINE	647 + 50		REMARKS
TOTAL	17.8 73.0 90.8	RT LT	652 + 10				TOTAL	32.0 32.0	LT			
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12" SQ_YD	LOCATION MAINLINE	649 + 00	to	654 + 50	WIDENING	5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY) FOOT	LOCATION MAINLINE	651 + 28	TO 651 + 57	REMARKS
TOTAL	500.0 427.8 175.0 56.7 1159.5	RT LT RT LT	649 + 00	to	654 + 50	WIDENING	TOTAL	36.0 36.0	RT			
			649 + 00	to	654 + 50	WIDENING	54213453	END SECTIONS 18" EACH	LOCATION MAINLINE	647 + 32		REMARKS
			651 + 05	TO	652 + 10	TEMP PATCH SOUTH OF PILING	TOTAL	1.0 1.0 2.0	LT LT	647 + 63		
			651 + 25	TO	652 + 10	WIDENING TO BE REMOVED AND REPLACED IN STAGING	54213879	END SECTIONS 24" EACH	LOCATION MAINLINE	651 + 57		REMARKS
35101400	AGGREGATE BASE COURSE, TYPE B TON	LOCATION MAINLINE	647 + 50			TEMPORARY FIELD ENTRANCE	TOTAL	1.0 1.0	RT			
TOTAL	594.0 594.0	LT					63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS FOOT	LOCATION MAINLINE	651 + 87	TO 654 + 00	REMARKS
							TOTAL	212.5 212.5	LT			