

GENERAL NOTES

A minimum of 2 air monitors will be required to monitor abrasive blasting operations, see special provision for "Containment and Disposal of Lead Paint Cleaning Residues".

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per LUMP SUM for CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of CLEANING AND PAINTING STEEL BRIDGE NO. 1.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the CLEANING AND PAINTING STEEL BRIDGE NO. 1.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities
3. General Notes, Index of Sheets, Standards
4. Traffic Control Plan
Existing Bridge Plans Structure No. 098-0083
5. General Plan & Elevation
6. Superstructure
7. Framing Plan
8. Bearings

STANDARDS

- 701101-02 Off-Road Operations, Multilane, 4.5 m (15') to 600 mm (24") From Pavement Edge
- 701301-03 Lane Closure, 2L, 2W, Short Time Operations
- 701400-04 Approach to Lane Closure, Freeway/Expressway
- 701402-07 Lane Closure, Freeway/Expressway, with Barrier
- 701406-05 Lane Closure, Freeway/Expressway, Day Operations Only
- 701901-01 Traffic Control Devices
- 704001-06 Temporary Concrete Barrier
- 720001-01 Sign Panel Mounting Details
- 720006-02 Sign Panel Erection Details
- 720011-01 Metal Posts for Signs, Markers and Delineators
- 728001-01 Telescoping Steel Sign Support
- 729001-01 Applications of Types A and B Metal Posts (For Signs & Markers)

FILE NAME =	USER NAME = lmkdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS, STANDARDS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BRV\Brdge Painting\Contract\PAINTING\64G19\PLANeng.dgn	DRAWN -	REVISED -	88			(195-3HB-3)P	Whiteside	8	3	
PLOT SCALE = 50.0000' / 1".	CHECKED -	REVISED -	CONTRACT NO. 64G19							
PLOT DATE = Tue Mar 16 06:42:58 2010	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
						SCALE: _____	SHEET NO. _____	OF _____ SHEETS	STA. _____	TO STA. _____