

IMPACT ATTENUATOR SCHEDULE			
LOCATION	IMPACT ATTENUATOR REMOVAL	IMPACT ATTEN. (NON-REDIRECTIVE) TEST LEVEL 3	FURNISHED EXCAVATION
	EACH	EACH	EACH
046-0081	2	2	5
046-0086	2	2	5
046-0085	2	2	5
046-0058	2	2	5
046-0084	2	2	5
046-0083	2	2	5
PROJECT TOTALS	12	12	30

-BARRELS TO BE PLACED ON EXISTING ATTENUATOR BASES IN SAME CONFIGURATION AS EXISTING.
 -ALL EXISTING ATTENUATORS SHALL BE TAKEN TO KANKAKEE MAINTENANCE YARD FOR SALVAGE-INCLUDED IN THE COST OF IMPACT ATTENUATOR REMOVAL
 -SEE IMPACT ATTENUATOR DETAILS FOR TYPICAL BARREL ARRAY DIAGRAM

LOCATION	FENCE			
	WOVE WIRE FENCE-4' FOOT	WOVE WIRE FENCE REMOVAL FOOT	CHAIN LINK FENCE-4' FOOT	CHAIN LINK FENCE REMOVAL FOOT
316.55	30	30		
316.65	50	50		
316.80	20	20		
317.20	50	50		
317.50	75	75		
317.55	30	30		
317.62	50	50		
317.75	50	50		
318.60	15	15		
318.70	75	75		
319.22	50	50		
319.40	15	15		
319.52	30	30		
319.90	50	50		
319.92	30	30		
320.00	30	30		
320.03	50	50		
320.04	30	30		
320.15	75	75		
320.25	50	50		
320.30	75	75		
322.40	30	30		
322.43	30	30		
Total N.B.	990.00	990.00		
LOG MILE S.B.				
318.70	100	100		
318.28	50	50		
317.60	30	30		
317.50	50	50		
317.48	50	50		
324.45	30	30		
324.25	50	50		
324.20	50	50		
324.18	30	30		
323.05	75	75		
322.55			75	75
321.6 (SB ENT RAMP)	50	50		
321.50	30	30		
321.25	50	50		
320.69	50	50		
320.60	200	200		
320.45	50	50		
320.35	100	100		
320.32	50	50		
319.70			75	75
318.98	50	50		
318.75	75	75		
Total S.B.	1220	1220	150	150
GRAND TOTAL	2210.00	2210.00	150.00	150.00

WOOD POSTS		
LOCATION**	REMOVE WOOD POST*	FURNISHING AND SETTING WOOD POST
	EACH	EACH
NORTHBOUND LANE		
STA 420+95 (ST GEORGE RD E5000N) SN 046-0081	10	20
STA 434+20	5	10
STA 447+45	5	10
STA 460+70	5	10
STA 474+00 (E6000N RD) SN 046-0086	10	20
STA 501+00	15	20
STA 528+18 (E 7000N RD) SN 046-0085	10	20
STA 641+33 (MANTENO RD) SN 046-0058	12	20
STA 697+81 (E 10000N RD) SN 046-0084	12	
STA 736+86	2	
STA 775+85	20	
STA 814+95 (E 12000N RD) SN 046-0083	20	
TOTALS	170	110

*NO NEW POSTS NEEDED BEHIND HTCMB
 **STATIONS ARE APPROXIMATE