

PATCHING SCHEDULE - SOUTHBOUND LANE

LOCATION M.P.	2 LANE PAVEMENT			4 LANE PAVEMENT - PL PASSING LANE			4 LANE PAVEMENT - PL DRIVING LANE		
	CLASS B TYPE II	DOWEL BARS	SAW CUTS	CLASS B TYPE II	DOWEL BARS	SAW CUTS	CLASS B TYPE II	DOWEL BARS	SAW CUTS
	SQ YD	EACH	FOOT	SQ YD	EACH	FOOT	SQ YD	EACH	FOOT
3.40	8	20	48						
3.50	8	20	48						
3.55	8	20	48						
3.80	8	20	48						
3.85	8	20	48						
3.88	8	20	48						
3.90	8	20	48						
4.30	START HMA OVERLY								
4.50	END HMA OVERLAY								
4.60	8	20	48						
4.65	8	20	48						
4.70	8	20	48						
4.90	8	20	48						
5.00	8	20	48						
5.10	8	20	48						
5.20	8	20	48						
5.40	8	20	48						
5.50	8	20	48						
6.10	8	20	48						
6.30	8	20	48						
6.50	8	20	48						
7.30	8	20	48						
7.40	8	20	48						
7.45	8	20	48						
7.60	8	20	48						
7.70	8	20	48						
7.90	8	20	48						
8.10	8	20	48						
8.20	8	20	48						
8.25	8	20	48						
8.30	8	20	48						
8.50	8	20	48						
8.55	8	20	48						
8.65	8	20	48						
8.85	8	20	48						
8.87	8	20	48						
9.10	8	20	48						
9.30	8	20	48						
9.35	8	20	48						
9.60	BEGIN HMA OVERLAY								
10.10	INTERSECTION US RTE. 24								
SB SUBTOTALS	296	740	1776						
SB TOTALS	640	1600	3840						