

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE	
				FAI RTE. 55 J000	IL RTE. 47 J000
20200500	EARTH EXCAVATION (WIDENING)	CU YD	14		14
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	257		257
40200700	AGGREGATE SURFACE COURSE, TYPE A, 8"	SQ YD	422		422
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	360		360
44000100	PAVEMENT REMOVAL	SQ YD	360		360
44003100	MEDIAN REMOVAL	SQ FT	335		335
44004250	PAVED SHOULDER REMOVAL	SQ YD	200		200
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	219	219	
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	28	28	
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SQ YD	470		470
44213000	PATCHING REINFORCEMENT	SQ YD	247	247	
44213200	SAW CUTS	FOOT	5058	1570	3488
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	257		257
60619600	CONCRETE MEDIAN TYPE SB6.12	SQ FT	335		335
67100100	MOBILIZATION	L SUM	1	0.75	0.25
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	970	370	600
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	169	57	112
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	12	12	
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	1	
Z0017202	DOWEL BARS 1 1/2"	EACH	1168		1168
Z0075310	TIE BARS 3/4"	EACH	10	10	

* SPECIALITY ITEM

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED -
c:\pwork\PIWIDOT\WOODSHANKRL\0188632	0366A39-details.dgn	DRAWN - RON WOODSHANK	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr 09, 2010 - 06:21:59 AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	D3 PATCHING 2011-6	GRUNDY	13	3
**	FAI 55 & FAP 326		CONTRACT NO. 66A39	
			[ILLINOIS]	