

PATCHING SCHEDULE - FAI 55											
LOCATION	PASSING LANE					DRIVING LANE					REMARKS
	CLASS A		PATCH REINF.	SAW CUTS	TIE BARS	CLASS A		PATCH REINF.	SAW CUTS	TIE BARS	
	TYPE II 9"	TYPE IV 9"				TYPE II 9"	TYPE IV 9"				
M.P.	SQ YD	SQ YD	SQ YD	FOOT	EACH	SQ YD	SQ YD	SQ YD	FOOT	EACH	
218.07											LIVINGSTON COUNTY LINE
218.40						8		8	60		
218.50						8		8	60		
218.80						11		11	64		
218.90						11		11	64		
218.91						11		11	64		
218.92						11		11	64		
219.10						8		8	60		
219.11						8		8	60		
219.40						8		8	60		
219.45						8		8	60		
219.70						8		8	60		
219.82											IL RTE. 47
220.30							28	28	90	10	
220.40						8		8	60		
220.50						8		8	60		
220.60						8		8	60		
220.65						13		13	68		
226.82											FAS RTE. 292 (GARDNER RD.)
233.30											WILL COUNTY LINE
NBL TOTALS						136	28	164	1014	10	

PATCHING SCHEDULE - FAI 55											
LOCATION	PASSING LANE					DRIVING LANE					REMARKS
	CLASS A		PATCH REINF.	SAW CUTS	TIE BARS	CLASS A		PATCH REINF.	SAW CUTS	TIE BARS	
	TYPE II 9"	TYPE IV 9"				TYPE II 9"	TYPE IV 9"				
M.P.	SQ YD	SQ YD	SQ YD	FOOT	EACH	SQ YD	SQ YD	SQ YD	FOOT	EACH	
233.49											WILL COUNTY LINE
226.82											FAS 292 (GARDNER RD.)
219.90						8		8	60		
219.85						8		8	60		
219.82											IL RTE. 47
219.80						8		8	60		
219.30						13		13	68		
219.31						13		13	68		
219.10						8		8	60		
218.60						8		8	60		
218.30						8		8	60		
218.25						8		8	60		
218.07											LIVINGSTON COUNTY LINE
SBL TOTALS						83		83	556		