

PATCHING SCHEDULE - IL 47							
LOCATION NBL	PASSING LANE			DRIVING LANE			REMARKS
	CLASS B TYPE II 14"	DOWEL BARS 1 1/2"	SAW CUTS FOOT	CLASS B TYPE II 14"	DOWEL BARS 1 1/2"	SAW CUTS FOOT	
	SQ YD	EACH		SQ YD	EACH		
0.00							BEGIN CONCRETE SECTION
0.01	8	20	60				
0.02	8	20	60	8	20	60	
0.03				8	20	60	
0.04				8	20	60	
0.06				8	20	60	
0.07				8	20	60	
0.10				8	20	60	
0.14	8	20	60	8	20	60	
0.18	8	20	60	8	20	60	
0.20				8	20	60	
0.21				8	20	60	
0.22				8	20	60	
0.35	8	20	60	8	20	60	
0.38	8	20	60				
0.38	8	20	60				TURN LANE
0.40	8	20	60				
0.42				8	20	60	
0.43	8	20	60				
0.45	8	20	60	8	8	60	
0.46	8	20	60				
0.47		20					
0.51							END CONCRETE SECTION
NBL TOTALS	88	240	660	112	268	840	

PATCHING SCHEDULE - IL 47							
LOCATION SBL	PASSING LANE			DRIVING LANE			REMARKS
	CLASS B TYPE II 14"	DOWEL BARS 1 1/2"	SAW CUTS FOOT	CLASS B TYPE II 14"	DOWEL BARS 1 1/2"	SAW CUTS FOOT	
	SQ YD	EACH		SQ YD	EACH		
0.00							BEGIN CONCRETE SECTION
0.01	8	20	60	8	20	60	
0.04	8	20	60	8	20	60	
0.07	8	20	60	8	20	60	
0.08				11	20	64	
0.10	8	20	60				
0.11				8	20	60	
0.12	8	20	60				
0.15				8	20	60	
0.16	8	20	60	8	20	60	
0.17				8	20	60	
0.18				8	20	60	
0.19				8	20	60	
0.19				8	20	60	
0.25	8	20	60				
0.26	8	20	60	8	20	60	
0.29	8	20	60				
0.30	8	20	60	8	20	60	
0.33	8	20	60	8	20	60	
0.33	8	20	60				TURN LANE
0.37	8	20	60				
0.40				8	20	60	
0.43	11	20	64	8	20	60	
0.47	8	20	60				
0.50	8	20	60	8	20	60	
0.51							END CONCRETE SECTION
SBL TOTALS	131	320	964	139	340	1024	

RAMP F RECONSTRUCTION SCHEDULE									
LOCATION	EARTH EXCAVATION WIDENING	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	STABILIZED SUB-BASE 4"	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDER 9"	AGGREGATE SURFACE COURSE TYPE A 8"	MEDIAN REMOVAL	CONCRETE MEDIAN TYPE SB6.12
	CU YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ FT	SQ FT
RAMP F	14	360	200	257	360	257	460	335	335