

SPL	CODE NO.	PAYITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITIES	SUMMARY OF QUANTITIES		H24				LS3E						
					H24	LS3E	H24		LS3E		H24		LS3E				
					I000	I000	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y030-1E			
					ROADWAY	ROADWAY	SIGNALS	SIGNALS	SIGNALS	SIGNALS	SIGNALS	SIGNALS	LIGHTING				
					80/20	90/10	80/13.3/6.7	90/10	90/10	90/10	90/10	90/10	90/10	90/10	90/10	90/10	90/10
							IL 29 & LASALLE	IL 29 & WESLEY				IL 29 & WESLEY					
							MARQ HTS	N. PEKIN	DET LOOPS								
	20200100	EARTH EXCAVATION	CU YD	555	555												
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1620		1620											
	21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	4040	4040												
	21400100	GRADING AND SHAPING DITCHES	FOOT	130	130												
	25000210	SEEDING, CLASS 2A	ACRE	0.85	0.85												
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77	77												
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	77	77												
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77	77												
	25100630	EROSION CONTROL BLANKET	SQ YD	4040	4040												
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	911	911												
	28000305	TEMPORARY DITCH CHECKS	FOOT	296	296												
	28000400	PERIMETER EROSION BARRIER	FOOT	1282	1282												
	28000500	INLET AND PIPE PROTECTION	EACH	2	2												
	28000700	MULCH, METHOD 1	ACRE	2.6	2.6												
	28100127	STONE RIPRAP, CLASS B4	SQ YD	100	100												
	28200200	FILTER FABRIC	SQ YD	100	100												
	31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1620		1620											
	35300705	PORTLAND CEMENT CONCRETE BASE COURSE 12 1/4"	SQ YD	985		985											
	40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	12	12												
	40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	707	707												
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1												
	40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	871	871												

FILE NAME = Summary of Quantities .dgn

USER NAME = jebabidjan	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/25/2010	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	(11)RS-9,L-2,N,TS-4	TAZEWELL	102	6
CONTRACT NO. 68590			ILLINOIS FED. AID PROJECT	