

TABULATION OF PATCHING QUANTITIES

LOCATION	SIZE	CLASS B, PATCHES, TY II, 15 INCH		CLASS B, PATCHES, TY III, 15 INCH		CLASS B, PATCHES, TY IV, 15 INCH		TIE BARS	DOWEL BARS	PAVEMENT FABRIC	SAWCUTS
		* OF PATCHES*	SQYDS	* OF PATCHES*	SQYDS	* OF PATCHES*	SQYDS	EACH	EACH	SQYDS	FOOT
<b>IL 29 (Northbound)</b>											
Sta 247+8 - Sta 8+50	6 X 12	16	128						320		864
	8 X 12	4	43						80		240
	12 X 12			6	96			18	120	96	432
	20 X 12					1	27		20	27	96
<b>IL 29 (Southbound)</b>											
Sta 247+8 - Sta 8+50	6 X 12	20	160						400		1080
	8 X 12	13	139						260		780
	12 X 12			6	96			18	120	96	432
	20X 12					1	27		20	27	96
	<b>SUBTOTAL</b>		469		192		53	36	1340	245	4020
	<b>10 % FOR WINTER BREAK-UP</b>		+ 10%		+ 10%		+ 10%	+ 10%	+ 10%	+ 10%	+ 10%
	<b>TOTAL</b>		516	<b>TOTAL</b>	211	<b>TOTAL</b>	59	40	1474	270	4422

\* OF PATCHES GIVEN ABOVE IS FOR INFORMATION ONLY, FIELD ENGINEER WILL VERIFY BEFORE THE BEGINNING OF CONSTRUCTION

TABULATION OF ROADWAY PAVEMENT REMOVAL

LOCATION	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CCC&G REMOVAL	ISLAND REMOVAL	MEDIAN REMOVAL	MEDIAN REMOVAL PARTIAL DEPTH
	SQYD	SQYD	FOOT	SQFT	SQFT	SQFT
<b>IL 29</b>						
Sta 242+97.5 - Sta 243+21.29				225.00		
Sta 243+71.24 - Sta 243+96.41				184.00		
Sta 244+30.5 - Sta 244+46.96				104.00		
Sta 244+31.77 - Sta 247+20.38					1820.00	
Sta 243+17 - Sta 4+81.3 *	107.17				4501.00	
<b>WESLEY RD</b>						
Sta 16+50 - Sta 18+47.46						1290.00
Sta 16+96.72 - Sta 17+64.86		107.78	134.00			
Sta 16+26. - Sta 18+11.98	123.33					
Sta 17+57.14 - Sta 0+47.88**	160.00					
Sta 18+81.42 - Sta 244+68 **	272.22					
Sta 17+31.81 - Sta 18+10.57		114.22				
Sta 18+07 - Sta 19+98			226.00			
<b>MAIN ST</b>						
Sta 20+08 - Sta 21+20			148.00			
Sta 21+20 - Sta 243+28.**	12.89					
** Sta 246+13 - Sta 21+24.8	190.00					
Sta 21+26.72 - Sta 22+68.2			120.00			
Sta 21+58 - Sta 22+20.28		57.00				
* Sta Equation 246+17 = 0+00						
** Use IL 29 Stationing for radii						
	<b>SUBTOTAL</b>	865.6	279.00	628.00	513.00	6321.00
	<b>TOTAL</b>	866.0	279.0	628.0	513.0	6321.0

FILE NAME = Schedules of Quantities.dgn

USER NAME = jebabidism	DESIGNED -	REVISED -
PLOT SCALE = 1/80.0000" = 1"	DRAWN -	REVISED -
PLOT DATE = 3/25/2010	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE. 669	SECTION (11RS-9,L-2,N,TS-4)	COUNTY TAZEWELL	TOTAL SHEETS 1219
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 68590	