

LOCATION	LENGTH	SHORT TERM PAVEMENT MARKING			WORK ZONE PAVEMENT MARKING REMOVAL
		* CENTERLINE SKIP (WHITE)	* SHOULDER STRIPE (WHITE / YELLOW)	* SOLID (WHITE)	AREA
		WHITE FEET	YELLOW FEET	WHITE FEET	YELLOW / WHITE SQ FT
IL 29					
Northbound Lanes					
STA 247+80 - STA 08+50	1413	2120	283	2910	358
Southbound Lanes					
STA 247+80 - STA 08+50	1413	2120	283	2940	360
Main St					
-				420	28
Wesley Rd					
-				1620	108
* 5 applications					
	SUB-TOTAL	4240	566	7890	854
	TOTAL		12696		854

LOCATION	URETHANE PAVEMENT MARKINGS					PREFORMED PLASTIC PAVEMENT MARKINGS			
	4 INCH SOLID		8 INCH SOLID	12 INCH SOLID		24 INCH SOLID	LETTERS & SYMBOLS	6 INCH SOLID	
	WHITE FEET	YELLOW FEET	WHITE FEET	WHITE FEET	YELLOW FEET	WHITE FEET	WHITE SQFT	WHITE FEET	
Mainline IL 29									
247 +50 - 8+50	2364.00	2475.00	1619.00	282.00	51.00	213.00	380.80	1070.00	
Wesley Rd									
	397.00	705.00	487.00	80.00		36.00	83.20		
Main St.									
	715.00	600.00	640.00	120.00		14.00	83.20		
	SUB-TOTAL	3476	3780	2746	482	51	263	547.2	1070
	TOTAL		7256	2746		533	263	548	1070

FILE NAME = Schedules of Quantities .dgn

USER NAME = lobebsdian

DESIGNED -

REVISED -

DRAWN -

REVISED -

CHECKED -

REVISED -

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:

SHEET NO. 4 OF 4 SHEETS

STA.

TO STA.

F.A.P. RTE.
669

SECTION
(11)RS-9L-2,N,TS-4

COUNTY
TAZEWELL

TOTAL SHEETS
102

SHEET NO.
23

CONTRACT NO. 68590

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT