



STA 14+70 TO STA 37+02

GAP CONCRETE SECTION STA 37+02 - 42+03

1. EXISTING 10" P.C.C. PAVEMENT
 2. EXISTING BRICK AND SAND LAYER
 3. EXISTING HOT-MIX ASPHALT OVERLAY 3"
 4. EXISTING HOT-MIX ASPHALT OVERLAY 5-1/2"
 5. EXISTING HOT-MIX ASPHALT OVERLAY 6-1/4"
 6. EXISTING P.C.C. BASE COURSE
 7. EXISTING COMB. CONC. CURB AND GUTTER
 8. EXISTING AREA REFLECTIVE CRACK CONTROL TREATMENT
 9. EXISTING HOT-MIX ASPHALT SHOULDER 6"
 10. EXISTING AGGREGATE SHOULDER
 11. EXISTING COMB CC & BASE CSE WIDENING 0'-4'
 12. EXISTING HOT-MIX ASPHALT BASE COURSE 10"
 13. EXISTING LEVELING BINDER VARIABLE THICKNESS
 14. EXISTING HOT-MIX ASPHALT OVERLAY 1-1/2"
-
- A. PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL 2"
 - B. PROPOSED POLYMERIZED LEVELING BINDER (MM), IL 4.75, N50, .75"
 - C. PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50, 1.5"
 - D. PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX C, N30 (SHOULDERS) 1.5"
 - E. PROPOSED AGGREGATE SHOULDERS, TYPE B

FILE NAME = D468743-CADD.dgn	USER NAME = tiesmondw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS			F.A.P. RTE. 656	SECTION (B)RS-3(L)RS-4	COUNTY TAZEWELL	TOTAL SHEETS 34	SHEET NO. 9
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -					CONTRACT NO. 68743				
	PLOT DATE = 3/15/2010	CHECKED -	REVISED -					ILLINOIS FED. AID PROJECT				
	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			