

SEEDING & FERTILIZER SUMMARY

LOCATION	TEMP EROS CONT SEED (lbs)	SEEDING CL 2A (ACRE)	EROS CONT BLKT(SQ YD)	NITROGEN FERT (LBS)	PHOSPHORES FERT. (LBS)	POTASSIUM FERT (LBS)	TOPSOIL FURN & PLACED, 4" (SQ YD)
STA 1401+50 TO	60	0.22	1034	20	20	20	722
TOTAL	60	0.22	1034	20	20	20	722

GUARDRAIL REMOVAL	FOOT
STA 1400+90 TO 1402+15 22' RT	125
TOTAL	125

FURNISHING & ERECTING ROW MARKERS		
LOCATION		EACH
1401+50	50'RT	1
1402+25	140'RT	1
1402+60	140'RT	1
1402+60	48'RT	1
TOTAL		4

TRAF CONT & PROT STD,701201	LUMP SUM
JOBSITE	1
TOTAL	1

CONCRETE REMOVAL CULVERT/HEADWALL	
LOCATION	CU YD
STA 1402+02.5	1.61
TOTAL	1.61

REMOVAL & DISPOSAL OF UNSUITABLE MATL BETWEEN EXISTING HEADWALL & MANHOLE	CU YD
	7.5
TOTAL	7.5

EARTHWORK				
LOCATION	EARTH EX (CUT) CU YD	ADJ EARTH EX (CUT) CU YD	EMBANK (FILL) CU YD	WASTE CU YD
STA 1401+50 TO 1402+60 RT	5	4	1177	-1173
TOTAL	5	4	1177	

NOTE: adjust earth ex calc's assuming 20% shrinkage factor

CONSTRUCTION LAYOUT	
LOCATION	LUMP SUM
JOBSITE	1

MOBILIZATION	
LOCATION	LUMP SUM
JOBSITE	1
TOTAL	1

FENCE REMOVAL	FOOT
STA 1400+ RT	15
TOTAL	15

TREE REMOVAL	ACRE
STA 1401+50 TO 1402+60 RT	0.18
TOTAL	0.18

INLET PIPE PROTECTION	EACH
STA 1402+35 70 RT	1
TOTAL	1

PERIM EROS BARRIER	FOOT
STA 1401+50 70 RT	260
TOTAL	260

TEMP DITCH CHECKS	EACH
STA 1401+50 TO 1402+60 RT	200
TOTAL	200