

SUMMARY OF QUANTITIES

DEWITT CO.
RURAL
TWO LANE
100% STATE
MINOR
STRUCTURE
REPAIR

SFTY-2A
S.N. 020-0045

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	47.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N-50	TON	143.0
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	470.0
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1070.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	1083.0
67100100	MOBILIZATION	L SUM	1.0
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0
* 78001110	PAINT PAVEMENT MARKING, LINE 4"	FOOT	781.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5.0
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5.0
X0320887	POLYMER CONCRETE	CU FT	14.5
X0321744	SILICONE JOINT SEALER, 2"	FOOT	90.0
X0322905	PRECAST PRESTRESSED CONCRETE I-BEAM REPAIRS	L SUM	1.0
X0325682	PUMPABLE CONCRETE MIX	CU FT	3.0
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	54.0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	160.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = simsgn	DESIGNED - GMS	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\FWIDOT\NSINGM\0179794\05703	31-shr-Bridge Repair Plans.dgn	DRAWN - GMS	REVISED - ----			760	124 BR-1	DEWITT	23	3	
	PLOT SCALE = 41.6516" / IN.	CHECKED - ----	REVISED - ----			CONTRACT NO. 70531					
	PLOT DATE = 2/19/2018	DATE - ----	REVISED - ----			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					