

LANDSCAPING SCHEDULE

| STATION | STATION | AREA (ACRE) | (25000200) | (25000350) | (25000400) | (25000500) | (25000600) | (25100115) | (28000250) |
|----------------|---------|----------------|------------------------------|------------------------------|-----------------------------------|------------------------------------|----------------------------------|-----------------------------|------------------------------------------|
| | | | SEEDING CLASS 2 (ACRE) | SEEDING CLASS 7 (ACRE) | NITROGEN FERTILIZER (POUND) | PHOSPHOR. FERTILIZER (POUND) | POTASS. FERTILIZER (POUND) | MULCH METHOD 2 (ACRE) | EROSION CONTROL SEEDING (POUND) |
| LT & RT 503+98 | 503+98 | 0.12 | 0.12 | 0.12 | 10.8 | 10.8 | 10.8 | 0.12 | 12.0 |
| LT & RT 557+48 | 558+52 | 0.14 | 0.14 | 0.14 | 12.6 | 12.6 | 12.6 | 0.14 | 14.0 |
| LT & RT 718+90 | 720+02 | 0.12 | 0.12 | 0.12 | 10.8 | 10.8 | 10.8 | 0.12 | 12.0 |
| TOTAL = | | 0.38 | 0.38 | 0.38 | 34.2 | 34.2 | 34.2 | 0.38 | 38.0 |
| USE = | | 0.40 | 0.40 | 0.40 | 35.0 | 35.0 | 35.0 | 0.40 | 38.0 |

PAINT PAVEMENT MARKING-LINE 4" (78001110)

4" SOLID (WHITE)

| STATION | TO | STATION | FOOT (x 2) |
|----------------|----|-----------|--------------|
| 504+48.14 | | 504+65048 | 34.6 |
| 557+77.44 | | 558+04.32 | 53.8 |
| 719+37 | | 719+62 | 50.0 |
| TOTAL = | | | 138.4 |
| USE = | | | 139.0 |

4" SKIP DASH (YELLOW)

| STATION | TO | STATION | FOOT |
|----------------------|----|-----------|--------------|
| 504+48.14 | | 504+65048 | 17.3 |
| 557+77.44 | | 558+04.32 | 26.9 |
| 719+37 | | 719+62 | 25.0 |
| TOTAL = | | | 69.2 |
| 69.2'/40*10 = | | | 17.3 |
| USE = | | | 17.0 |
| TOTAL = | | | 156.0 |

TEMPORARY DITCH CHECKS (28000305)

| STATION | Q/S | FOOT |
|----------------|--------|--------------|
| 504+06.81 | 36' RT | 12.0 |
| 504+06.81 | 34' LT | 12.0 |
| 505+06.81 | 37' RT | 12.0 |
| 505+06.81 | 37' LT | 12.0 |
| 557+40.90 | 37' RT | 12.0 |
| 557+40.90 | 36' LT | 12.0 |
| 558+40.90 | 35' RT | 12.0 |
| 558+4.090 | 35' LT | 12.0 |
| 719+50.00 | 40' RT | 12.0 |
| 719+50.00 | 39' LT | 12.0 |
| 720+00.00 | 40' RT | 12.0 |
| 720+00.00 | 38' LT | 12.0 |
| TOTAL = | | 144.0 |

PERIMETER EROSION BARRIER (28000400)

| STATION | STATION | FEET |
|----------------|-----------|--------------|
| 503+98 R | 505+02 RT | 104.0 |
| 503+98 LT | 505+02 LT | 104.0 |
| 557+48 R | 558+02 RT | 54.0 |
| 557+48 LT | 558+02 LT | 54.0 |
| 718+90 R | 720+02 RT | 112.0 |
| 718+90 LT | 720+02 LT | 112.0 |
| TOTAL = | | 540.0 |

INLET & PIPE PROTECTION (28000500)

| STATION | Q/S | EACH |
|----------------|--------|------------|
| 504+56.81 LT | 44.96' | 1.0 |
| 557+90.90 LT | 45.55' | 1.0 |
| 719+50.00 LT | 39.94' | 1.0 |
| TOTAL = | | 3.0 |

EXPLORATION TRENCH, 52" DEPTH (21301052)

| | STATION | STATION | LENGTH (FT) |
|----------------|---------|---------|----------------|
| LT | 504+32 | 504+82 | 50.0 |
| RT | 504+32 | 504+82 | 50.0 |
| LT | 557+66 | 558+16 | 50.0 |
| RT | 557+66 | 558+16 | 50.0 |
| LT | 719+26 | 719+76 | 50.0 |
| RT | 719+26 | 719+76 | 50.0 |
| TOTAL = | | | 300.0 |