

LOCATION OF WORK:

FAP 676 (US 150)
 STA. 42+19.48 TO
 STA. 256+00.00
 URBAN 4 LANE
 MCLEAN COUNTY

CONSTRUCTION TYPE CODE:

100% STATE
 I000
 TOTAL

CODE NO	ITEM	UNIT	QUANTITY
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25,246.0
40600300	AGGREGATE (PRIME COAT)	TON	370.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7,514.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,216.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	5,859.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6,092.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	5,179.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	875.0
40800030	AGGREGATE (PRIME COAT)	TON	18.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	980.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	994.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	36.0
44003800	MEDIAN SURFACE REMOVAL	SQ FT	1,109.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	465.0
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	296.0
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	40.0
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	53.0
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	5.0
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	48.0
44213100	PAVEMENT FABRIC	SQ YD	93.0

* SPECIALTY ITEM(S)

(CONT'D NEXT SHEET)

FILE NAME :	USER NAME = sherer,jm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cl:\pw\work\PW100T\SHERRERJM\0109813\05768-shr-500.dgn	PLOT SCALE = 100.0000 / IN.	DRAWN - JMS	REVISED -		676	19-1,9/RS	MCLEAN	81	5				
	PLOT DATE = 3/2/2010	CHECKED - JMS	REVISED -		SCALE:	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 70768				
		DATE - 061809	REVISED -		ILLINOIS FED. AID PROJECT								