

LOCATION OF WORK:

FAP 676 (US 150)  
 STA. 42+19.48 TO  
 STA. 256+00.00  
 URBAN 4 LANE  
 MCLEAN COUNTY

CONSTRUCTION TYPE CODE:

100% STATE  
 1000  
 TOTAL

CODE NO	ITEM	UNIT	QUANTITY
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1342.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE4"	FOOT	91145.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE6"	FOOT	2233.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1441.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	754.0
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING,TYPE B - LINE4"	FOOT	7488.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	702.0
* 78200405	GUARDRAIL MARKERS	EACH	20.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	702.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1016.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	281.0
X4421000	PARTIAL DEPTH PATCHING	TON	47.0
Z0012500	CONCRETE CURB REPAIR	FOOT	284.0
Z0017100	DOWEL BARS	EACH	840.0
Z0075300	TIE BARS	EACH	70.0

\* SPECIALTY ITEM(S)

FILE NAME =	USER NAME = shera-jm	DESIGNED - JMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cs:\pwwork\pwidot\shera-jm\0189813\0570768-shr-500.dgn		DRAWN - JMS	REVISED -		676	19-1,9/RS	MCLEAN	81	7				
PLOT SCALE = 100.0000' / IN.		CHECKED - JMS	REVISED -		CONTRACT NO. 70768								
PLOT DATE = 2/25/2010		DATE - 061809	REVISED -		SCALE:	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				