

**GENERAL NOTES**

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-442B – PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-780 SPECIAL

PAINT PAVEMENT MARKINGS SHALL BE APPLIED UPON COMPLETION OF THE PATCH WORK. PAINT PAVEMENT MARKINGS SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. PAINT PAVEMENT MARKINGS SHALL BE LIMITED ONLY TO LENGTH SEGMENTS ASSOCIATED WITH INDIVIDUAL PATCH LOCATIONS AND SHALL NOT BE APPLIED CONTINUOUSLY THROUGH THE PROJECT BETWEEN PATCH LOCATIONS.

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

NO COMMITMENTS

FILE NAME =	USER NAME = coombessf	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\COOMBESSF\0179854\0570816-sht:gennote.dgn		DRAWN -	REVISED -		322	D5 PATCHING 2011-1	*	25	3				
PLOT SCALE = 40,0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 70816								
PLOT DATE = 3/17/2010		DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT					