

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE									
				ROADWAY				TRAFFIC SIGNALS		LIGHTING		SIDEWALK	
				FAP 67	FAP 75	FAP 668	FAI 72	CLRLAKE DIRKSEN	CLRLAKE HILL	FAP 67	FAP 75	FAP 67	FAP 668
				1000-2A				Y03I-IF		Y030-IE		SFTY-IB	
44000100	PAVEMENT REMOVAL	SQ YD	4218	3365	296	557							
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	31659	12327			19332						
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	32719	18604	7384	6731							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3749	2454	335	960							
44000300	CURB REMOVAL	FOOT	414	414									
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15423	9379	3499	2545							
44000600	SIDEWALK REMOVAL	SQ FT	68									68	
44002805	ISLAND REMOVAL	SQ FT	1330	1330									
44003100	MEDIAN REMOVAL	SQ FT	28864	17188	7399	4277							
44004000	PAVED DITCH REMOVAL	FOOT	123	123									
44004250	PAVED SHOULDER REMOVAL	SQ YD	322	322									
44201847	CLASS D PATCHES, TYPE I, 17 INCH	SQ YD	4	4									
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	23	23									
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	18	18									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	295	118		177							
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	267	267									
48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	9397	3694		5703							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	103	103									
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6									
50105220	PIPE CULVERT REMOVAL	FOOT	313	313									
50901760	PIPE HANDRAIL	FOOT	294	154		140							
51604000	DRILLED SHAFT IN ROCK	CU YD	99	57	42								
54213447	END SECTIONS 12"	EACH	4	4									
54213459	END SECTIONS 24"	EACH	4	4									
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	1	1									
54248510	CONCRETE COLLAR	CU YD	1.6	1.0		0.6							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	2445	2337		108							
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	272	272									
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	238	238									
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	116	116									
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	47	47									
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	458	458									
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	389	389									
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	459	459									
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	194			194							

VARIOUS ROUTES

100% STATE

F.A.P. 72, F.A.P. 67, F.A.P. 75 & F.A.P. 668
D-6 SPFLD-CLRLAKE DIRKSEN 2002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SANGAMON	363	5
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 72088				

* DENOTES SPECIALTY ITEM

SHEET 2 OF 7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY MLO
CHECKED BY SJK

DATE 08/05