

STATION/LOCATION	FACING	SIGN NO. (MUTCD)	SIZE	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 3 SQ FT	MESSAGE	REMOVE SIGN PANEL SQ FT	REMOVE SIGN PANEL ASSEMBLY EACH	RELOCATE SIGN PANEL TYPE 1 SQ FT	RELOCATE SIGN PANEL TYPE 2 SQ FT	NUMBER OF POSTS EACH	TELESCOPING STEEL SIGN SUPPORT FOOT	BASE FOR TELESCOPING STEEL SIGN SUPPORT EACH	REMOVE SIGN SUPPORT EACH	OBJECT MARKER TYPE 1 EACH
FAP 668 DIRKSEN PARKWAY (CONTINUED)																
169+95	7.8' LT	NORTH	R3-I100L 24"X24"	4			LEFT TURN LANE					1	9	1		
170+23	0' C	NORTH	R4-7 24"X30"	5			KEEP RIGHT (SYMBOL)					1	9.5	1		1
172+33	53' LT	WEST	R1-1 30"X30"	6.25			STOP					1	14.5			
NORTH FRONTAGE ROAD																
9+99.41	LT	SOUTH	R11-I100 48"X30"		10		ROAD ENDS					3	27	3		2
SOUTH FRONTAGE ROAD																
9+44	22.4' RT	WEST	R1-1 30"X30"	6.25			STOP					1	14.5			
	22.4' RT	WEST	R1-3A 12"X6"	0.50			3 WAY									
10+52	44.6' RT	SOUTH	R1-1 30"X30"	6.25			STOP					1	14.5			
	44.6' RT	SOUTH	R10-7 24"X30"	5.00			DO NOT BLOCK INTERSECTION									
	44.6' RT	SOUTH	R1-52A 30"X12"	2.50			ON COMING TRAFFIC DOES NOT STOP									
10+63	22.6' LT	EAST	R1-1 30"X30"	6.25			STOP					1	14.5			
	22.6' LT	EAST	R1-3A 12"X6"	0.50			3 WAY									
14+68	52.4' RT	SOUTH	R1-1 30"X30"	6.25			STOP					1	12.5			
15+52	15.2' RT	WEST	R1-1 30"X30"	6.25			STOP					1	14.5			
16+20	16.6' RT	SOUTH	R1-1 30"X30"	6.25			STOP					1	14.5			
16+36	21' LT	EAST	R1-1 30"X30"	6.25			STOP					1	15			
SHEET SUB-TOTALS				67.5	10	0		0	0	0	0	13	160	5	0	3
CLEAR LAKE/DIRKSEN SIGNAL PLANS					52.5											
HILL STREET/CLEAR LAKE SIGNAL PLANS				15	30.0											
TOTALS				381.0	102.5	0		6.5	1	8	10	60	690	35	4	11

NOTE:
 SEE TRAFFIC SIGNAL PLANS FOR SIGN DETAILS AND QUANTITIES FOR "CLEAR LAKE AVE", "DIRKSEN PARKWAY", AND "HILL ST" SIGN PANELS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		PERMANENT SIGNING SCHEDULE DRAWN BY RJC CHECKED BY DATE 01/08

c:\pw\work\pwidot\LAUGHLINR\p0183446\SignSched.dgn
 DATE