

CODE NO.	ITEM	UNITS	TOTAL QUANTITY 100% STATE	CONSTRUCTION CODE					
				BROWN COUNTY			SCHUYLER COUNTY		
				ROADWAY HMA RESURFACING STA. 52+00 TO STA. 420+00.00	ROADWAY NEW CONSTRUCTION STA. 420+00.00 TO STA. 434+34.07	BRIDGE SN 005-0000 STA. 434+34.07 TO STA. 439+03.24	ROADWAY NEW CONSTRUCTION STA. 439+03.24 TO STA. 452+80.20 BK. = STA. 452+78.48 AH. TO STA. 454+00.00	ROADWAY HMA RESURFACING STA. 454+00.00 TO STA. 459+53.00	ROADWAY HMA RESURFACING STA. 459+53.00 TO STA. 469+00.00 AND IL103 INTERSECTION
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1			
50104400	CONCRETE HEADWALL REMOVAL	EACH	2		2.0				
50105220	PIPE CULVERT REMOVAL	FOOT	179		74		105		
50200100	STRUCTURE EXCAVATION	CU YD	655			655			
50300225	CONCRETE STRUCTURES	CU YD	301.8			301.8			
50300225	CONCRETE SUPERSTRUCTURE	CU YD	699.8			699.8			
50300260	BRIDGE DECK GROOVING	SQ YD	1992			1992.0			
50300280	CONCRETE ENCASEMENT	CU YD	12.6			12.6			
50300300	PROTECTIVE COAT	SQ YD	2538.0			2538.0			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0			1.0			
50500505	SHEAR STUD CONNECTORS	EACH	3600.0			3600			
50800105	REINFORCEMENT BARS	POUND	20760.0			20760			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	200830.0			200830			
50800515	BAR SPLICERS	EACH	386.0			386			
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	1445.0			1445			
51202305	DRIVING PILES	FOOT	1445.0			1445			
51203600	TEST PILE STEEL HP 12X53	EACH	2.0			2			
51204650	PILE SHOES	EACH	36.0			36			
51500100	NAME PLATES	EACH	1.0			1			
51603000	DRILLED SHAFT IN SOIL	CU YD	73.5			73.5			
51604000	DRILLED SHAFT IN ROCK	CU YD	34.7			34.7			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	86			86.0			
52100020	ELASTOMERIC BEANING ASSEMBLY, TYPE 11	EACH	12			12.0			
52100520	ANCHOR BOLTS, 1"	EACH	24			24.0			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24			24			
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	56				56		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	68		68				
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	50		50				
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	70					70	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	94				94		
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	58		58				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2		2				

\* 9RS-4, (10,11)RS-3; (10B-1)R  
 \*\* BROWN, SCHUYLER

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
es:\pwwork\VP\VIDOT\LAUGHLINR1\dms20637\672432-shr-seq.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF	SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	*	**	196	6
			CONTRACT NO. 72432	
ILLINOIS FED. AID PROJECT				