

**PAVEMENT SCHEDULE**

LOCATION STATION TO STATION	LENGTH (FT)	PROPOSED WIDTH (FT)	HOT-MIX ASPHALT SURF REM BUTT - JOINT (SQ YD)	HOT-MIX ASPHALT SURF REMOV (VAR. DEPTH) (SQ YD)	HOT-MIX ASPHALT SURF REMOV (2 1/4") (SQ YD)	1' -6" SAFETY SHLD HOT-MIX ASPHALT SHOULDERS (6") (SQ YD)	EXCAVATING & GRADING EXIST. SHOULDERS (UNIT)	LEVEL BINDER (MM) N50 (3/4") (TON)	HOT-MIX ASPHALT SURF CSE "C" N50 (1 1/2") (TON)	BIT MAT PRIME CT (TON)	AGG PRIME CT (TON)
FAP 317 (US 24)											
STA. 51+70.0 TO STA. 76+56.68	2,486.68	25.00	83.3	6824.1				286.0	580.3	2.6	13.6
STA. 76+56.6 TO STA. 81+68.70	512.02	22.00		1164.8				52.6	105.1	0.5	2.5
STA. 81+68.7 TO STA. 88+56.00	687.30	22.00			1853.0			70.6	141.1	0.6	3.4
STA. 88+56.0 TO STA. 97+30.50	874.50	25.00		2331.9				102.0	204.1	0.9	4.9
STA. EQ. STA. 97+30.50 (BK) = STA. 97+73.16 (AH)											
STA. 97+73.1 TO STA. 184+77.9	8,704.74	25.00		24179.8				1,015.6	2,031.1	9.2	48.4
STA. EQ. STA. 184+77.90 (BK) = STA. 184+92.93 (AH)											
STA. 184+92. TO STA. 309+15.0	12,422.07	25.00		34505.8				1,449.3	2,898.5	13.1	69.0
STA. 309+15. TO STA. 420+00.0	11,085.00	25.00		27096.7		3,695.0	221.7	1,293.4	2,586.5	11.7	61.6
OMISSION FOR BRIDGE REMOVAL & REPLACEMENT STA. 420+00.00 TO STA. 454+00.00											
STA. 454+00. TO STA. 459+53.0	553.00	22.00		1351.8		-	11.1	57.0	113.5	0.5	2.7
STA. 459+53. TO STA. 460+53.0	100.00	22.00	-	244.4		-	2.0	10.3	20.5	0.1	0.5
STA. 460+53. TO STA. 462+93.0	240.00	VAR. 22.00 TO 34.00	-	586.7		-		31.4	62.7	0.3	1.5
STA. 462+93. TO STA. 467+77.5	484.50	34.00	-	1184.3		-	7.4	77.0	153.7	0.7	3.7
STA. 467+77. TO STA. 469+30.0	152.50	VAR. 34.00 TO 22.00	73.3	299.4		-	2.8	20.0	40.0	0.2	1.0
FAP 612 (IL 103)											
QUANTITIES FROM STA. 0+00.00 TO STA. 0+26.70 ARE INCLUDED IN US 24											
Sta 0+26.70 TO STA. 1+24.00	97.30	VARIES	-			-	-	35.5	70.9	0.3	1.7
STA. 1+24.00 TO STA. 5+00.00	376.00	VAR. 32.00 TO 23.00	127.9	383.3		-	4.0	48.3	96.5	0.4	2.3
<b>TOTAL</b>			284.5	100,153.0	1,853.0	3,695.0	249.0	4,549	9,104.5	41.5	217

**TEMPORARY RAMPS**

LOCATION STATION TO STATION	DESCRIPTION	AREA (SQ YD)
US 24		
STA. 52+00	BUTT JOINT	14
US 24 469+00	BUTT JOINT	12.5
SIDE ROADS		
RT. STA. 76+31		33.5
LT. STA. 79+81		21.0
LT. STA. 89+13		13.0
RT. STA. 117+30		22.5
LT. STA. 117+30		22.5
RT. STA. 177+58		33.5
RT. STA. 187+69		28.0
LT. STA. 231+58		28.0
RT. STA. 276+84		28.0
LT. STA. 176+84		19.5
OLD US 24 LT. STA. 313+93.84		39.0
RT. STA. 379+04.28		56.0
LT. STA. 379+04.28		56.0
LT. STA. 390+50.64		19.5
RT. STA. 407+00		22.5
JACKSON ST. LT. STA. 410+40		33.0
OLD US 24 RT. STA. 412+40		56.0
RIPLEY RT. STA. 414+25		39.0
LT. STA. 464+47.46		50.0
IL 103 STA. 450+00		13.0
<b>TOTAL</b>		660

**THERMOPLASTIC PAVEMENT MARKING - LINE SCHEDULE**

STATION TO STATION	DESCRIPTION	LINE 5"		LINE 6" WHITE (FOOT)	LINE 8" WHITE (FOOT)	LINE 12"	
		WHITE (FOOT)	YELLOW (FOOT)			WHITE (FOOT)	YELLOW (FOOT)
<b>INTERSECTION US 24 &amp; IL 103</b>							
FAP 317 (US 24)							
LT. STA 459+53.00 TO LT. STA 463+84.00	LEFT EDGE LINE, SOLID	431.0	-	-	-	-	-
LT. STA 465+11.00 TO LT. STA 469+30.00	LEFT EDGE LINE, SOLID	419.0	-	-	-	-	-
RT. STA 459+53.00 TO RT. STA 465+55.00	RIGHT EDGE LINE, SOLID	602.0	-	-	-	-	-
RT. STA 465+55.00 TO RT. STA. 1+57.00 (IL 103)	RIGHT EDGE LINE, SOLID	231.0	-	-	-	-	-
LT. 1+05.00 (IL 103) TO RT. STA 468+15.00	RIGHT EDGE LINE, SOLID	132.0	-	-	-	-	-
RT. STA 468+15.00 TO RT. STA 469+30.00	RIGHT EDGE LINE, SOLID	115.0	-	-	-	-	-
RT. STA 462+93.00 TO RT. STA 465+81.00	TURN LANE LINE, SOLID	-	-	288.0	-	-	-
RT. STA 465+81.00 TO RT. STA 466+33.00	ISLAND EDGE LINE, SOLID	-	-	-	180	-	-
RT. STA 465+81.00 TO RT. STA 466+33.00	ISLAND DIAGONALS, SOLID	-	-	-	-	40	-
RT. STA 466+73.50 TO RT. STA 467+50.00	ISLAND EDGE LINE, SOLID	-	-	-	208	-	-
RT. STA 466+73.50 TO RT. STA 467+50.00	ISLAND DIAGONALS, SOLID	-	-	-	-	94	-
FAP 612 (IL 103)							
STA 0+49.00 TO STA 3+06.00	MEDIAN LINE, SOLID DOUBLE	-	1036.0	-	-	-	-
STA 0+49.00 TO STA 3+06.00	MEDIAN, DIAGONALS SOLID	-	-	-	-	-	41
LT. STA 1+05.00 TO LT. STA 5+00.00	LEFT EDGE LINE, SOLID	395.0	-	-	-	-	-
RT. STA 1+57.00 TO RT. STA 5+00.00	RIGHT EDGE LINE, SOLID	346.0	-	-	-	-	-
<b>SUB - TOTALS</b>		2671.0	1036.0			134.0	41.0
<b>TOTAL</b>			3707.0	288.0	388.0		175.0

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
es:\pwork\pwidot\LAUGHLINRL\dms20637\672432-ah-t-sch.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.
--------	-----------	----	--------	------	----	------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	*	**	196	20
<b>CONTRACT NO. 72432</b>				
ILLINOIS FED. AID PROJECT				

\* 9RS-4, (10,11)RS-3; (10B-1)R  
\*\* BROWN & SCHUYLER COUNTIES