

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	1000-2A ROADWAY	Y030-1E LIGHTING												
80400100	ELECTRIC SERVICE INSTALLATION		EACH	5		5												
81021330	CONDUIT PUSHED, 2" DIA., PVC		FOOT	1270		1270												
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		FOOT	2010		2010												
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		FOOT	5794		5794												
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE		FOOT	1184		1184												
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE		FOOT	1655		1655												
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	6983		6983												
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT		EACH	49		49												
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT		EACH	9		9												
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP		EACH	4		4												
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP		EACH	1		1												
* 83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM		EACH	49		49												
83057280	LIGHT POLE, WOOD, 50 FOOT, CLASS 3		EACH	9		9												
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'		EACH	49		49												
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN		EACH	196		196												
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE		EACH	8		8												
Z0005010	HOT-MIX ASPHALT FOR PATCHING POTHOLES (COLD MIX)		TON	75	75													
Z0007601	BUILDING REMOVAL NO. 1		L SUM	1	1													
Z0007602	BUILDING REMOVAL NO. 2		L SUM	1	1													
Z0007603	BUILDING REMOVAL NO. 3		L SUM	1	1													
Z0007604	BUILDING REMOVAL NO. 4		L SUM	1	1													
Z0007605	BUILDING REMOVAL NO. 5		L SUM	1	1													
Z0007606	BUILDING REMOVAL NO. 6		L SUM	1	1													
Z0013798	CONSTRUCTION LAYOUT		L SUM	1	1													
Z0038506	REMOVE PERMANENT BARRICADES		L SUM	1	1													
Z0054530	ROCK FILL - SUBGRADE		TON	2000	2000													

* SPECIALTY ITEM

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 8 OF 9
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY: SEB
DATE: 8/22/06 CHECKED BY: TLD

5-25-10