

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				80% FED. 20% STATE TOTAL QUANTITIES		80% FEDERAL 20% STATE CONSTRUCTION AND SAFETY TYPE CODE							
CODE NO.	ITEM	SP. PROV.	UNIT			1000-2A ROADWAY	Y030-1E LIGHTING						
28100725	STONE DUMPED RIPRAP, CLASS B3		SQ YD		3121	3121							
28200200	FILTER FABRIC		SQ YD		669	669							
30103000	SHAPING AND GRADING ROADWAY		UNIT		119	119							
30200650	PROCESSING MODIFIED SOIL 12"	*	SQ YD		217951	217951							
30201500	LIME	*	TON		4354	4354							
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	*	TON		750	750							
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C		TON		15004	15004							
35100500	AGGREGATE BASE COURSE, TYPE A 6"		SQ YD		820	820							
35100700	AGGREGATE BASE COURSE, TYPE A 8"		SQ YD		11334	11334							
35100900	AGGREGATE BASE COURSE, TYPE A 10"		SQ YD		3840	3840							
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"		SQ YD		1714	1714							
35501331	HOT-MIX ASPHALT BASE COURSE, 11 3/4"		SQ YD		3135	3135							
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"		SQ YD		163	163							
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"		SQ YD		183	183							
40200100	AGGREGATE SURFACE COURSE, TYPE A		TON		1549	1549							
40300200	BITUMINOUS MATERIALS (PRIME COAT)		TON		6.5	6.5							
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)		TON		18.3	18.3							
40300500	COVER COAT AGGREGATE		TON		83	83							
40300600	SEAL COAT AGGREGATE		TON		46	46							
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON		225.8	225.8							
40600300	AGGREGATE (PRIME COAT)		TON		10	10							
40600895	CONSTRUCTING TEST STRIP		EACH		5	5							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SQ YD		56	56							
40600990	TEMPORARY RAMP		SQ YD		385	385							
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70		TON		1370	1370							
40701866	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/4"	*	SQ YD		9816	9816							

REVISIONS	
NAME	DATE
HMA SURF	3/25/2010

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 2 OF 9
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY
 SCALE: NONE DRAWN BY SEB
 DATE 8/22/06 CHECKED BY TLD

MAY 25 2010 8:33:02PM

SETL