

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE						
					I000-2A ROADWAY	Y030-1E LIGHTING					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"		FOOT	7144	7144						
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"		FOOT	1270	1270						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"		FOOT	245	245						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	58359	58359						
72000100	SIGN PANEL - TYPE 1		SQ FT	1597	1597						
72000200	SIGN PANEL - TYPE 2		SQ FT	255	255						
72000300	SIGN PANEL - TYPE 3		SQ FT	103	103						
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY		POUND	1134	1134						
72800100	TELESCOPING STEEL SIGN SUPPORT		FOOT	3757	3757						
73000100	WOOD SIGN SUPPORT		FOOT	141	141						
73400100	CONCRETE FOUNDATIONS		CU YD	8.4	8.4						
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		SQ FT	250	250						
78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	328	328						
78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT	116968	116968						
78001130	PAINT PAVEMENT MARKING - LINE 6"		FOOT	435	435						
78001150	PAINT PAVEMENT MARKING - LINE 12"		FOOT	151	151						
78001180	PAINT PAVEMENT MARKING - LINE 24"		FOOT	169	169						
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS		SQ FT	1186	1186						
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"		FOOT	11365	11365						
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"		FOOT	7043	7043						
78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"		FOOT	916	916						
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"		FOOT	202	202						
78100100	RAISED REFLECTIVE PAVEMENT MARKER		EACH	731	731						
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER		EACH	926	926						
78300100	PAVEMENT MARKING REMOVAL		SQ FT	2630	2630						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		EACH	965	965						

MS-15-2018 8/21/2024

*

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 7 OF 9
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY
 SCALE: NONE DRAWN BY SEB
 DATE 8/22/06 CHECKED BY TLD

Rev.